

SURVEY NARRATIVE

REPLACEMENT OF MONUMENTS DESTROYED BY HIGHWAY IMPROVEMENT PROJECT

LOCATED IN THE NORTHWEST ¼ OF SECTION 22, THE
NORTHEAST ¼ OF SECTION 21 AND THE SOUTH ½ OF SECTION 16
TOWNSHIP 36 SOUTH, RANGE 3 WEST
WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON

During the Downtown Gold Hill paving project, five center line monuments were destroyed. Utilizing the control and recovered monument positions per filed county survey # 17498, destroyed monuments were reset as described below:

The following monuments were replaced:

1074 Located at the intersection of Highway 234 (Second Avenue) and Seventh Street, was replaced with a 16mm x 762mm iron rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case. Note: Seventh Street was renamed to Gustaf Street.

1075 Located at the intersection of Highway 234 (Second Avenue) and Sixth Street, was replaced with a 16mm x 762mm iron rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case. Note: Sixth Street was renamed to Fredenburg Street.

1076 Located at the intersection of Highway 234 (Second Avenue) and Fifth Street, was replaced with a 16mm iron x 762mm rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case. Note: Fifth Street was renamed to Estremado Street.


1077 Located at the intersection of Highway 234 (Second Avenue) and Fourth Street was replaced with a 16mm x 762mm iron rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case. Note: Fourth Street was renamed to Dardanelles Street.

1078 Located at the intersection of Highway 234 (Second Avenue) and Third Street, was replaced with a 16mm x 762mm iron rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case. Note: Third Street was renamed to Chavner Street.

A monument case was placed at Fourth Avenue and Fourth Street. (Dardanelles St.) over existing monument, # 1008.

Equipment: Leica TCA 1800 Total Station with an angular error of +/- 1 second, and a standard distance error of +/- 2mm, +2ppm.

Field work was completed in January 2005.



RENEWS: 12/31/2005

CEIVED **

1-05 BY *BCB*

Survey Consists of:

Sheet(s) Map

Page(s) Narrative

JACKSON COUNTY
SURVEYOR