

SURVEY NARRATIVE
 REPLACEMENT OF MONUMENTS DESTROYED BY HIGHWAY
 IMPROVEMENT PROJECT
 LOCATED IN THE SOUTH 1/2 OF SECTION 29
 AND THE NORTHWEST 1/4 OF SECTION 32
 TOWNSHIP 37 SOUTH, RANGE 2 WEST
 WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON

During construction of the Downtown Jacksonville paving project, seven center line monuments were destroyed. Utilizing the control and recovered monument positions per filed county survey # 17499, destroyed monuments were reset as described below:

The following monuments were replaced:

- # 1000 Located at the intersection of Highway 238 (5th Street) and Shafer Lane, was replaced with a 16mm x 305mm iron rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case.
- # 1113 Located at the intersection of Highway 238 (5th Street) and "G" Street, was replaced with a 16mm x 610mm iron rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case.
- # 1112 Located at the intersection of Highway 238 (5th Street) and "E" Street, was replaced with a 16mm iron x 610mm rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case.
- # 1111 Located at the intersection of Highway 238 (5th Street) and "C" Street, was replaced with a 16mm iron x 381mm rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case.
- # 1109 Located at the intersection of Highway 238 (California Street) and 3rd Street was replaced with a 16mm x 203mm iron rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case.
- # 1108 Located at the intersection of Highway 238 (California Street) and Oregon Street, was replaced with a 16mm x 381mm iron rod / 37mm Brass disc stamped "ODOT CONTROL" set in monument case.
- # 1110 Could not be reset because of a new storm sewer manhole. Four reference monuments were set in the sidewalk. See sketch below. Reference monuments are 28mm bronze disc's stamped "ODOT CONTROL".

Equipment: Leica TCA 1800 Total Station with an angular error of +/- 1 second, and a standard distance error of +/- 2mm, +2ppm.

Field work was completed in January 2005.

NOT TO SCALE

REGISTERED PROFESSIONAL LAND SURVEYOR
Stuart E. Cappello
 OREGON
 JULY 09, 2001
 STUART E. CAPPELLO
 No. 52908

RENEWS: 12/31/2005

RECEIVED
 2-11-05 By *BB*
 survey Consists of:
 — sheet(s) Map
 — page(s) Narrative
 JACKSON COUNTY SURVEYOR

