

PLAT OF SURVEY
 LOCATED IN
 THE NW 1/4, NE 1/4, SEC. 25, T. 38 S., R. 2 W., W.M.
 JACKSON COUNTY, OREGON
 MAY 29, 2005

1/4 CORNER COMMON TO SECTIONS 24 AND 25
 FD. 1987 COUNTY BRASS CAP
 B.T.'S PER SURVEY NO. 1702 IN 1960/61:
 A 14 IN. DIAM. D.FIR BEARS S 18° E, 14.10 FT.
 A 11 IN. DIAM. B.OAK BEARS N 59° W, 7.92 FT.
 B.T. PER COUNTY FIRST RE-ESTABLISHMENT:
 FD. 12 IN. DIAM. B.OAK BEARS S 75° E, 80.95 FT.
 NEW B.T.:
 A 14 IN. DIAM. B.OAK BEARS N 42° E, 25.43 FT.
 SCRIBED "1/4 BT".

EAST 1/16 COR OF SECTIONS 24 AND 25
 FD. 5/8 IN. DIAM. I.ROD PER SURVEY NO. 7206.
 NEW B.T.'S:
 A 16 IN. DIAM. MADRONE BEARS N 88° E, 11.32 FT.
 SCRIBED "1/16 BT".
 A 12 IN. DIAM. D.FIR BEARS S 26° E, 20.07 FT.
 SCRIBED "1/16 BT".

(N 89°21'04" E 1357.98' PER PARTITION PLAT NO. P-23-1993)
 (N 89°21'04" E 1357.98' PER SURVEY NO. 7206)
 N 89°21'04" E 1357.92'



SCALE: 1" = 100'

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Raymond W. Wytcherley

OREGON
 JULY 25, 1995
 RAYMOND W. WYTCHERLEY
 2724

EXPIRES JUNE 30, 2006

LEGEND:

- INDICATES MONUMENT FOUND AS INDICATED.
- △ INDICATES CALCULATED POINT.
- () INDICATES RECORD AS NOTED.
- [] INDICATES RECORD PER GLO PLAT.

———— INDICATES LINES MARKED THIS SURVEY.

BASIS OF BEARING PER SURVEY NO. 7206.

PLOTTED BY A HP DESIGNJET 500 ON
 CONTINENTAL IMAGING # JPC4M2 POLYESTER
 FILM WITH HP CARTRIDGE # 4844A.

NARRATIVE:
 THE PURPOSE OF THIS SURVEY IS TO MARK THE NORTH LINE OF
 THE NW 1/4 OF THE NE 1/4 OF SECTION. 25, TOWNSHIP 38 SOUTH,
 RANGE 2 WEST, WILLAMETTE MERIDIAN. I FOUND AND HELD THE
 MONUMENTS AS SHOWN ON THIS PLAT.
 THIS SURVEY WAS PERFORMED USING A NIKON DTM 520
 TOTAL STATION USING A FULL SET OF DIRECTIONAL ANGLES.

SURVEYED FOR:
 MERIWETHER SOUTHERN OREGON
 LAND & TIMBER, LLC
 572 PARSONS DRIVE, SUITE 124
 MEDFORD, OREGON 97501

SURVEYED BY:
 RAYMOND WYTCHERLEY
 WYTCHERLEY SURVEYING
 P.O. BOX 888
 GLENDALE, OR 97442
 541-832-3286
 541-660-2648

** RECEIVED **

Date 6-17-05 By RS

This survey consists of:
1 sheet(s) Map
0 page(s) Narrative

JACKSON COUNTY
 SURVEYOR