

PUBLIC WORKS DEPARTMENT



CITY OF MEDFORD

MEDFORD, OREGON

April 2, 1962

Mr. Mark Boyden
County Surveyor
Jackson County Court House
Medford, Oregon

Dear Mark:

Attached is a narrative for the City of Medford Engineering Department constructing a concrete monument and placing a brass disc to replace the one-inch iron pipe for the 1/4 section corner between Section 28 and 33, Township 37 S., Range 1 W., Willamette Meridian, lying east of the intersection of Barnett Road and Murphy Road.

This monument was set in order to identify it as there is an iron pin set in concrete 27.73 feet south of this 1/4 corner, which might be mistaken by someone for the 1/4 corner.

We hope that this narrative description is sufficient for your requirements.

Very truly yours,

Vernon Thorpe
Public Works Director

VT:ms

Attachment

NARRATIVE FOR MONUMENTING 1/4 CORNER

SECTION $\frac{28}{33}$ T 37 S, R 1 W, WM.

Found the quarter corner for Sections 28 and 33, T. 37 S., R. 1 W. to be a 1" galvanized iron pipe with a wooden plug and a cup tack for center.

Set four straddle hubs with tacks in centers.

Removed 1" galvanized iron pipe and dug hole 25" deep to hard pan.

Replaced pipe with concrete monument and City of Medford brass disc with punch mark in the center and stamped,

$$\begin{array}{r} \frac{1}{4} S \ 28 \\ \hline \frac{1}{4} S \ 33 \\ T. \ 37 \ S. \ R. \ 1 \ W. \end{array}$$

Buried 5/8" x 24" iron pin in the concrete monument for ease in locating with pipe finder.

This quarter corner is approximately 125 feet East of the P.I. of the first curve east of Murphy Road and N 3° 58' W, 27.73 feet from the 5/8" iron pin in concrete.

(F.B. 2006 - R Pg. 55)

Submitted by: Vernon Thorpe
Public Works Director
City of Medford
April 2, 1962