

MAP OF SURVEY

LOCATED IN
THE SOUTHWEST QUARTER OF
THE NORTHEAST QUARTER OF SECTION 11,
TOWNSHIP 35 SOUTH, RANGE 4 WEST,
WILLAMETTE MERIDIAN,
JACKSON COUNTY, OREGON

SURVEY FOR:
ROCKY O. WARDLE
9525 EAST EVANS CREEK ROAD
ROGUE RIVER, OREGON 97537

SURVEY BY:
SMITH SURVEYING
LLOYD "BUTCH" SMITH
7050 HIGHWAY 140
EAGLE POINT, OREGON 97524
(541) 826-2509

15 DECEMBER 2006



E 1/16 CORNER (S 89°34'48" W 275.12')
S 89°32'50" W 275.18'

LEGEND

- FOUND 5/8" IRON PINS w/CAPS PER F.S. 5961.
- ◆ FOUND 5/8" IRON PINS w/CAPS PER F.S. 14737.
- ▲ CALCULATED POSITION.
- SET 5/8"x24" IRON REBAR w/PLASTIC CAP STAMPED "LS 2011".
- (...) RECORD DATA PER F.S. 5961.
- [...] RECORD DATA PER DOCUMENT NO. 78-09056.
- F.S. FILED SURVEY, JACKSON COUNTY SURVEYOR'S OFFICE.
- W.C. WITNESS CORNER.

PURPOSE OF SURVEY

TO SURVEY AND SET DEED CORNERS AS REQUESTED BY CLIENT.

PROCEDURE

FROM SURVEY MONUMENTS SET PER F.S. 5961 AS INDICATED ON MAP, THE 1/16 CORNERS WERE HELD FOR CONTROL, DEED CORNERS SET AS SHOWN. EXISTING CENTERLINE OF EAST EVANS CREEK ROAD WAS SURVEYED AND WITNESS CORNERS WERE SET ON NORTHERLY RIGHT-OF-WAY LINE.

