



MAP OF SURVEY
PROPERTY LINE ADJUSTMENT
 Located in the Section 18, T.99S, R.2E, W.M.
 Jackson County, Oregon
 (File No. SUB2006-00121)

SURVEY FOR:
 LEON PYLE
 460 SUNSHINE CIRCLE
 ASHLAND, OR 97520

SURVEY BY:
 L.J. FRIAR & ASSOCIATES, P.C.
 CONSULTING LAND SURVEYORS
 816 WEST EIGHTH STREET
 MEDFORD, OREGON 97501
 PHONE: (541) 772-2782
 EMAIL: ljfriar@charter.net

LEGEND:

- ⊙ = FD. COUNTY SURVEYOR'S BRASS CAPPED MONUMENT PER RE-ESTAB'S.
- = FD. 3/4" REBAR [5/8" IRON ROD]. SEE FS18101.
- = SET 5/8" X 30" IRON PIN W/ PLASTIC CAP MKD. L.J. & ASSOC. AS WITNESS CORNER.

JCDR = JACKSON COUNTY DEED RECORDS.
 ORJCO = OFFICIAL RECORDS OF JACKSON COUNTY, OREGON.
 () = RECORD DATA PER DOC. 2004-005187, ORJCO.
 FS = FILED SURVEY #.
 -X- = FENCE LINE.
 [] = RECORD DATA PER FS18101.

BASIS OF BEARINGS:

FS18101 AS SHOWN HEREON.

UNIT OF MEASUREMENT = FEET DATE: APRIL 9, 2007 SCALE: 1" = 200'

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.260

PURPOSE: TO SURVEY AND MONUMENT THE ADJUSTED PROPERTY LINE CREATED THROUGH A PROPERTY LINE ADJUSTMENT. SEE COUNTY FILE SUB2006-00121.

PROCEDURE: MADE TIES TO MONUMENTS OF RECORD AS SHOWN HEREON TO CONTROL THE EXTERIOR OF THE EXISTING TL301 (DOC. 2004-057910, ORJCO). COMPUTED THE POSITION OF THE ADJUSTED LINE AT THE LOCATION APPROVED BY COUNTY PLANNING AND SET MONUMENT AS A WITNESS CORNER AS SHOWN HEREON. THE EXTERIOR OF TL200 (DOC. 2004-005187, ORJCO) WAS COMPUTED USING DEED RECORD DATA. THE IMPROVEMENTS SHOWN ON TL200 ARE APPROXIMATELY LOCATED USING JACKSON COUNTY SMARTMAP AERIAL PHOTOGRAPHS. PREPARED LEGAL DESCRIPTIONS OF THE RESULTANT TRACTS FOR USE IN THE PREPARATION OF ADJUSTMENT DEEDS.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
James E. Hibbs
 OREGON
 JULY 17, 1986
 JAMES E. HIBBS
 2234
 EXPIRES 6-30-07

*** RECEIVED ***
 DATE 5-11-07 BY *[Signature]*
 This survey consists of:
 1 sheet(s) Map
 0 page(s) Narrative
 JACKSON COUNTY
 SURVEYOR

*** JACKSON COUNTY PLANNING ***
 FILE NO. SUB2006-000121

EXAMINED AND APPROVED THIS 20th DAY OF April 2007.

BY: *[Signature]*