Partition Plat No. P- 42-2007

(AND LOT LINE ADJUSTMENT)

OF PARCEL NO. 1 & 2 OF PARTITION PLAT P-60-2005

LYING WITHIN
THE SOUTHWEST 1/4 OF SECTION 16,
TOWNSHIP 34 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN,
CITY OF SHADY COVE, JACKSON COUNTY, OREGON

ASSESSOR'S MAP NO.: 34-1W-16CA TL's 1405, 1406

DECLARATION		SURVEYOR'S CERTIFICATE		
KNOW ALL MEN BY THESE PRESENTS THAT WE, MARK E. BARBER AND LAURA A. BARBE OREGON CORPORATION, ARE THE OWNERS OF THE LANDS REPRESENTED ON THIS PARTIT SURVEYOR'S CERTIFICATE AND HAVE CAUSED THE SAME TO BE PARTITIONED INTO PARCE PUBLIC FOR PUBLIC USE THE 10-FOOT WIDE PUBLIC UTILITY EASEMENT, AS SHOWN HERE AND UTILITY EASEMENTS ACROSS PARCELS 2, 3 AND 5 FOR THE BENEFIT OF PARCELS	LS, AS SHOWN HEREON, AND DO HEREBY DEDICATE TO THE	I, KERRY K. BRADSHAW, A DULY REGISTERED SURVEYOR IN THE STATE OF OREGON, DO HEREBY CERTIFY THAT THIS PLAT CORRECTLY REPRESENTS A SURVEY MADE BY ME AND COMPLIES WITH THE REGULATIONS FOR LAND PARTITIONS AND THE FOLLOWING IS AN ACCURATE DESCRIPTION OF THE PARENT TRACT AS SET FORTH HEREON.		
MARK BARBER, PRESIDENT OF BARBER HOMES, INC. MARK E. BARBER	LAURA A. BARBER	PARCELS NUMBER 1 AND 2 OF PARTITION PLAT RECORDED AUGUST 22, 2005 IN THE "RECORDS OF PARTITION PLATS" OF JACKSON COUNTY, OREGON AS PARTITION PLAT NO. P-60-2005 AND FILED IN THE OFFICE OF THE JACKSON COUNTY SURVEYOR AS SURVEY NO. 18860.		
STATE OF OREGON) (SS) (COUNTY OF JACKSON)	~ ~	REGISTERED PROFESSIONAL LAND SURVEYOR I CERTIFY THIS TO BE AN EXACT COPY OF THE ORIGINAL PLAT. REGISTERED PROFESSIONAL LAND SURVEYOR		
THE FOREGOING INSTRUMENT WAS ACKNOWLEDGED BEFORE ME THIS DAY OF PRESIDENT OF BARBER HOMES, INC., AN OREGON CORPORATION, AND ACKNOWLEDGED THE NOTARY PUBLIC		OREGON JULY 16, 1987 KERRY K. BRADSHAW 2271 EXP. 12-31-07		
383868 9-22-2008 COMMISSION NO. MY COMMISSION EXPIRES		FILED FOR RECORD THIS 12 DAY OF JUNE 2007 AT 1:42 O'CLOCK P M. AND RECORDED AS		
STATE OF OREGON)) SS COUNTY OF JACKSON)		PARTITION PLAT No. $P-42-2007$ of the "records of partition plats" in Jackson county, oregon.		
THE FOREGOING INSTRUMENT WAS ACKNOWLEDGED BEFORE ME THIS DAY OF ACKNOWLEDGED THIS TO BE HIS VOLUNTARY ACT AND DEED.	May , 2007, BY MARK E. BARBER AND	INDEX VOLUME 18 PAGE 42		
NOTARY PUBLIC PRINTED NAME	nin-	Kathleen 5 Beckett COUNTY CLERK Koben Thompson DEPUTY		
383868 9-22-2008 COMMISSION NO. MY COMMISSION EXPIRES		FILED IN THE OFFICE OF THE JACKSON COUNTY SURVEYOR AS SURVEY No. 19666		
STATE OF OREGON)) SS COUNTY OF JACKSON)		NARRATIVE		
THE FOREGOING INSTRUMENT WAS ACKNOWLEDGED BEFORE ME THIS 2/ DAY OF ACKNOWLEDGED THIS TO BE HER VOLUNTARY ACT AND DEED. Carol Sarta		PURPOSE: TO MONUMENT A LOT LINE ADJUSTMENT OF THE NORTH LINE OF PARCEL 2 OF PARTITION PLAT NO. P-60-2005 AND THEN PARTITION PARCELS NUMBER 1 AND 2 OF PARTITION PLAT NO. P-60-2005 AS DIRECTED BY THE CLIENT AND AS APPROVED BY THE CITY OF SHADY COVE PLANNING DEPARTMENT. PROCEDURE:		
383868		A NIKON DTM 520 TOTAL STATION WAS USED TO TIE FOUND MONUMENTS FROM FILED SURVEY NUMBERS 6979, 17807, 10888 AND 18860. SAID FOUND MONUMENTS WERE USED TO CONTROL THE BOUNDARY, AS SHOWN HEREON. THE PARCELS WERE MONUMENTED PER CLIENT INSTRUCTION AND THIS PLAT PREPARED.		
APPROVALS		TAX STATEMENT		
CITY OF SHADY COVE PLANNING DEPARTMENT DATE		all fees, taxes, assessments or other charges as required by o.r.s. 92.095 have been paid as of fune 12, 2007. Carol July 10 6-12-07 LAX COLLEGES ASSESSMENTS OR OTHER CHARGES AS REQUIRED BY O.R.S. 92.095 HAVE BEEN PAID AS OF JUNE 12, 2007. ASSESSMENTS OR OTHER CHARGES AS REQUIRED BY O.R.S. 92.095 HAVE BEEN PAID AS OF JUNE 12, 2007.		
EXAMINED AND APPROVED THIS ZIET DAY OF May , 2007. JACKSON COUNTY SURVEYOR	2 - 1 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 -	TIMBERLINE LAND SURVEYING, INC.		
AFFIDAMT OF CONSENT		LAND SURVEYING-WATER RIGHTS KERRY K. BRADSHAW, P.L.S C.W.R.E. CHARLES R. SMITH, P.L.S. P.O. BOX 3064 PHONE: (541) 664-2878 CENTRAL POINT, OREGON 97502 FAX: (541) 664-7863		

FOR AFFIDAVIT OF CONSENT FROM BANK OF THE CASCADES SEE INSTRUMENT NO. 2007 027590 OF THE OFFICIAL RECORDS OF JACKSON COUNTY, OREGON.

19666

SHEET 1 OF 2

BARBER HOMES, INC

P.O. BOX 1335, SHADY COVE, OREGON 97539

JOB #: 07-014

DATE: 05-11-07


DRAWN BY: TEB

CHECKED BY: KKB

PREPARED

FOR:

FILE NAME: 2007\07-014 Barber\final.dwg



Partition Plat No. P-42-2007

(AND LOT LINE ADJUSTMENT)

PARCEL NO. 1 & 2 OF PARTITION PLAT P-60-2005

LYING WITHIN

THE SOUTHWEST 1/4 OF SECTION 16, TOWNSHIP 34 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN, CITY OF SHADY COVE, JACKSON COUNTY, OREGON

CURVE	RADIUS	ARC LENGTH	CHORD LENGTH	CHORD BEARING	DELTA ANGLE
C1	120.00'	6.31'	6.31'	S 50°12'57" E	03'00'42"
(RECORD)	(120.00')	(6.307')	(6.307')	(S50°11'02"E)	(03'00'43')
C2	120.00'	80.21'	78.72'	S 70'52'11" E	38'17'47"
(RECORD)	(120.00')	(80.208')	(78.723')	(S70°50'16"E)	(38-17-47")
C3	80.00'	62.85'	61.24'	N 67°24'39" W	45'00'39"
C4	80.00'	62.85'	61.24'	N 22"24'00" W	45'00'39"
C5	80.00'	44.09'	43.53'	N 15'55'17" E	31°34'33"
(RECORD)	(80.00')	(44.099')	(43.543')	(N15'53'29"E)	(31°35'02")
C6	28.00'	24.84	24.04'	N 25'29'32" E	50'50'00"
C7	48.00'	235.97'	60.63'	S 89'55'28" E	281'40'00"
C8	28.00'	24.84'	24.04'	S 25'20'28" E	50'50'00"
C9	80.00'	125.69'	113.16'	N 44°54'20" W	90'01'17"
(RECORD)	(80.00')	(125.783')	(113.222')	(S44*56'36"E)	(90.05,08,)
C10	120.00'	86.52'	84.65'	S 69'21'50" E	41"18'29"
(RECORD)	(120.00')	(86.516')	(84.654')	(S69'19'55"E)	(41'18'30")
C11	48.00'	125.76'	92.75'	N 24'17'54" E	150'06'44"
C12	48.00'	20.47'	20.32'	S 68°25'40" E	24'26'09"
C13	48.00'	20.82'	20.66'	S 43'46'56" E	24'51'19"
C14	48.00'	68.92'	63.15'	S 09'46'37" W	82°15'48"

BASIS OF BEARINGS

THE MONUMENTED NORTHWESTERLY RIGHT-OF-WAY OF ROGUE AIR DRIVE SHOWN AS S3179'19"W ON PARTITON PLAT NO. P-60-2005 (FS 18860).

ENCUMBRANCE NOTES

THE POWER LINE EASEMENTS GRANTED PER VOLUME 90, PAGE 610, AND INSTRUMENT NUMBERS 85-19996, 96-21956 AND 03-76840 MAY AFFECT THIS PROPERTY, BUT ARE NOT LOCATABLE.

THE EASEMENTS FOR AIRPORT LANDING STRIP PURPOSES AND INGRESS/EGRESS CREATED BY INSTRUMENT 71-05264 MAY AFFECT THIS PROPERTY, BUT ARE NOT

THE INGRESS/EGRESS EASEMENTS RECORDED IN INSTRUMENT NUMBERS 73-09325 AND 79-25111 APPEARS TO BE FOR ROGUE AIR DRIVE.

INSTRUMENT NO. 2005-053295 RESERVES A 10-FOOT EASEMENT RUNNING ALONG PARTITION PLAT P-60-2005 LOT LINES BORDERING A SHARED DRIVEWAY TO HELP ENSURE ADEQUATE WING CLEARANCE FOR TAXING AIRCRAFT.

PARCELS NO. 1 AND 3 OF PARTITION PLAT NO. P-60-2005 ARE SUBJECT TO THE TERMS AND PROVISIONS OF THE WATER SYSTEM MAINTENANCE AGREEMENT RECORDED AS INSTRUMENT NO. 2005-053296.

O - FOUND %" REBAR PER FS 18860

△ - FOUND ¾" IRON PIN IN CONCRETE PER FS 6979
□ - FOUND ¾" IRON PIN PER FS 6979

♦ - FOUND % REBAR PER FS 10888 - FOUND % REBAR PER FS 17807

SET %" X 24" REBAR WITH YELLOW PLASTIC CAP STAMPED "BRADSHAW, LS 2271"

FS - FILED SURVEY IN THE OFFICE OF THE JACKSON COUNTY SURVEYOR

) - RECORD DATA PER PARTITION PLAT NO. P-60-2005

WM - WITNESS MONUMENT

COPY OF THE ORIGINAL PLAT.

REGISTERED PROFESSIONAL LAND SURVEYOR

Kerry K. Kr OREGON JULY 16, 1987 KERRY K. BRADSHAW 2271

EXP. 12-31-07

TIMBERLINE LAND SURVEYING, INC. LAND SURVEYING-WATER RIGHT'S KERRY K. BRADSHAW, P.L.S. - C.W.R.E. CHARLES R. SMITH, P.L.S. PHONE: (541) 664-2878

P.O. BOX 3064 CENTRAL POINT, OREGON 97502

FAX: (541) 664-7863

PREPARED DATE: 05-11-07

BARBER HOMES, INC P.O. BOX 1335, SHADY COVE, OREGON 97539

FILE NAME: 2007\07-014 Barber\final.dwg SHEET 2 OF 2