



MAP OF SURVEY

located in the
 NORTHEAST ONE QUARTER OF THE
 NORTHWEST ONE QUARTER OF SECTION 32,
 TOWNSHIP 37 SOUTH, RANGE 2 WEST,
 WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON
 for

ERIC AND LISA ARTNER

P.O. BOX 609
 JACKSONVILLE, OREGON 97530

LEGEND

- x-x- = FENCE
- BASIS OF BEARING IS TRUE NORTH, NAD 83/91 DATUM, AS DERIVED BY GLOBAL POSITIONING SYSTEM OBSERVATIONS.
- ⊙ = SET TACK & WASHER MARKED "LS 2189"
- = SET 5/8" x 24" IRON PIN w/ YELLOW PLASTIC CAP MARKED "FARBER PLS 2189"
- W.C. = WITNESS CORNER

SURVEY NARRATIVE
 TO COMPLY WITH O.R.S. 209.250

PURPOSE: TO SURVEY AND MONUMENT THE BOUNDARY DESCRIBED IN INSTRUMENT 1994-39756 AND INSTRUMENT 1994-39757.

PROCEDURE: UTILIZING GLOBAL POSITIONING SYSTEM CONTROL, I TIED THE RECOVERED MONUMENTS AS SHOWN. HOLDING THE CENTERLINE MONUMENTS, I LOCATED THE RIGHT-OF-WAY PER PLAT RECORDS. THE LOTS WERE THEN LOCATED BY PORPORTIONING THE SUBDIVISION BLOCKS PER PLAT RECORD OF THE TOWN PLAT OF THE CITY OF JACKSONVILLE.

Surveyed by:

FARBER & SONS, INC.
 dba FARBER SURVEYING
 (541) 664-5599
 PO BOX 5286
 431 OAK STREET
 CENTRAL POINT, OREGON 97502

SCALE: 1" = 30'



DATE: OCTOBER 11, 2007
 JOB NO.: 0438-94

DRAWING FILE: X:\JOBS\Jacksonville\ARTNER-JUBILEE\MicroSurvey\site map 092507.dwg
 DRAWN BY: AMP ORIG. DATE: 10/11/2007 REVISED BY: XXX DATE: XX/XX/XXXX

** RECEIVED **
 DATE 10-15-07 BY [Signature]
 This survey consists of:
 1 sheet(s) Map
 2 page(s) Narrative
 JACKSON COUNTY
 SURVEYOR

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

[Signature]
 OREGON
 JULY 26, 1985
 HERBERT A. FARBER
 2189

RENEWAL DATE 12-31-07