

W 1/16TH

1/4 COR.

23

26

FD. UNRECORDED
1/2" IRON PIPE 9" DEEP
N 24°41'53" W 11.0'

O.R. 86-14060

TOPBANK OF APPIEGATE RIVER

N 89°30'15" E 330.00

N 89°30'15" E 1330.29 (N 89°30'15" E 1330.31) << N 89°30'08" E 20.154 CH>>

S 00°37'22" E 330.00

S 00°37'22" E 1283.56 (S 00°37'22" E 1283.59) << S 00°37'23" E 19.447 CH>>

F.S. # 15256

NE 1/4 OF THE NW 1/4 OF SECTION 26

S 01°56'26" E 1294.77 (S 01°56'26" E 1294.79)

TOPBANK OF APPIEGATE RIVER

WIT. COR.

N 89°57'32" E 1000.00

N 89°57'32" E 1360.15 (N 89°41'13" E 1360.16)

NW 1/16TH

CALC. CN 1/16TH

NARRATIVE

PURPOSE: To survey and mark the true lines of a portion of Instrument number 86-14060 and Instrument number 85-22075 of the Official Records of Jackson County, Oregon.

PROCEDURE: I found and tied B.L.M. monuments marking the corners of the Northeast Quarter of the Northwest Quarter of Section 26. Ties to the corners of the Northeast Quarter of the Northwest Quarter checked very close to filed survey number 15256 and the B.L.M. record. I calculated and set monuments at the Southeast and Southwest corners of said Instrument number 86-14060. The Southeast corner lands on the approximate top of bank of the Applegate River. The South line was marked with flo-pink ribbon. I then ran and blazed line from the Southwest corner of the Northeast Quarter of the Northwest Quarter Easterly along the South line of said Northeast Quarter of the Northwest Quarter, 1000.00 feet to a witness corner monument set on the approximate top of bank of the Applegate River.

LEGEND

- SET 5/8" X 30" REBAR WITH PLASTIC CAP MARKED 'TEMPLIN LS2359'
- STANDARD B.L.M. BRASS CAP MONUMENT
- △ INDICATES CALCULATED POSITION
- < > INDICATES RECORD DATA PER FS 15256
- << >> INDICATES RECORD DATA PER OFFICIAL B.L.M. SURVEY
- FS INDICATES FILED SURVEY
- INDICATES TRUE LINE MARKED

BASIS OF BEARING: THE BEARINGS ARE BASED UPON FILED SURVEY NUMBER 15256.



SCALE: 1"=100'

FILE: 'HEAD.dwg'

****RECEIVED****
 DATE: 11-16-07 BY: *bb*
 This survey consists of:
 1 sheet(s) Map
 0 page(s) Narrative
JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
RT
 OREGON
 JULY 26, 1988
 RICHARD G. TEMPLIN
 2359
 MY CERTIFICATE EXPIRES JUNE 30, 2008

RICHARD TEMPLIN LAND SURVEYING
P.O. BOX 1946 899-2032 JACKSONVILLE, OREGON

MAP OF SURVEY

LOCATED IN
IN THE NE 1/4 OF THE NW 1/4 OF SECTION 26,
T.38S., R.4W., W.M., JACKSON COUNTY, OREGON

For: Mr. Dan Head
P.O. Box 3255
Applegate, Or. 97530

DATE: Nov. 11, 2007