

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: A. F. Reed and Ally Sheldon
Scenic Avenue
Central Point, Oregon

LOCATION: DLC #61, Section 33, T36SR2W, W.M.

PURPOSE: To establish a division line through that tract jointly-owned by Reed and Sheldon described in Volume 331, Page 313 of the Deed Records of Jackson County, Oregon.

A description was then to be prepared of said division line, so that each owner could deed his interest in the overall property lying Easterly or Westerly from said division line.

PROCEDURE:


The subject tract, with minor variations, was surveyed and recorded as Survey No. 214. Said survey found none of the DLC corners which control the subject property exterior boundaries, therefor leaving the true position of said boundaries in question.

It was decided for the purpose of this survey, to accurately monument and describe the division line as shown, but assume no responsibility as to the true position of the exterior boundaries of the overall tract.

Began at the 2" iron pipe monument found for the Northwest corner of Section 33, and traversed Southeasterly to and around the subject tract. Ties were made to monuments found, and a traverse run between monuments set by Reed and Sheldon to control the division line.

The position of the division line was then computed and described.

Meridian was established by a solar observation.



September 1962

