



MAP
 SHOWING A SURVEY IN THE N.W. 1/4
 OF THE N.W. 1/4 OF SEC. 13, T. 36
 S., R. 4 W., W.M., JACKSON CO., OR.

SURVEYED FOR:
 JUDY BEAUMONT
 P.O. BOX 535
 ROGUE RIVER, OREGON

SURVEYED BY:
 MAX H. HULL SURVEYING
 231 N.W. "B" STREET
 GRANTS PASS, OREGON

NUMBER	DELTA ANGLE	RADIUS	TANGENT	ARC LENGTH	CHORD LENGTH	CHORD DIRECTION
C1	03°19'51"	1492.40	43.39	86.76	86.74	S 12°18'23" W
C2	06°04'58"	776.20	41.24	82.41	82.37	S 17°15'00" W
C3	06°13'06"	746.20	40.53	80.99	80.95	S 25°05'41" W
C4	06°09'59"	716.20	38.58	77.08	77.04	S 25°07'14" W
C5	07°49'44"	716.20	49.01	97.86	97.79	S 18°07'23" W
C6	03°19'51"	1432.40	41.65	83.27	83.26	S 12°18'23" W

- SET 5/8" X 30" IRON ROD WITH YELLOW PLASTIC CAP MARKED "HULL RS 901"
- FOUND IRON MONUMENT PER JACKSON COUNTY DEPT. OF PUBLIC WORKS SURVEY OF WARDS CREEK ROAD DATED APRIL 1975 UNLESS OTHERWISE NOTED.
- CALCULATED POSITION
- INDICATES LINE BRUSHED, FLAGGED WITH YELLOW AND ORANGE FLAGGING AND MARKED WITH 3" HIGH STEEL FENCE POSTS.
- () RECORD PER S/N 16618
- < > RECORD PER S/N 16244
- [] RECORD PER JACKSON COUNTY DEPT. OF PUBLIC WORKS SURVEY OF WARDS CREEK ROAD DATED APRIL 1975.
- S/N FILED SURVEY No. IN THE OFFICE OF THE JACKSON COUNTY SURVEYOR
- BASIS OF BEARING PER S/N 16244
- MAP: 36-4W-13
- TAX LOT: 301
- SCALE: 1" = 50'
- DATE: JUNE 19, 2009

NARRATIVE

THE PURPOSE OF THIS SURVEY IS TO SURVEY, MONUMENT AND MARK A PORTION OF THE BOUNDARIES OF THAT PROPERTY DESCRIBED IN DEED DOCUMENT No. 2004-052478, JACKSON COUNTY OFFICIAL RECORDS; THENCE USING SAID DEED AND MONUMENTS AS SHOWN FOUND ON THE MAP, I SURVEYED, MONUMENTED AND MARKED THE PROPERTY LINES AS INDICATED. THE SURVEY WAS CONDUCTED WITH A NIKON DTM-522 TOTAL STATION.

•• RECEIVED ••
 Date: 6-30-09 By: MB
 This survey consists of:
 1 sheet(s) Map
 0 page(s) Narrative
 JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
 Max H. Hull
 OREGON
 JULY 11, 1969
 MAX H. HULL
 901
 RENEW: JUNE 30, 2009