



SURVEY IN SEC. 31 T. 36 S., R. 1 W., W.M.
 FOR
 C. HOOVER
 62-17-A

BY EDWARD MC GINTY
 MEDFORD OREGON
 NOVEMBER 1962

SCALE 1" = 300'
 O = 5/8" I. PIN
 X = 3/4" I. PIN



Survey Narrative to comply with O.R.S. 209-250.

Survey for: Claude Hoover
Rt. 2, Box 227, Medford.

Survey by: Edward A. McGinty, L.S.
11/11/62

BASIS OF BEARING: Solar Observation.

PRECEDENCE OF SURVEY:

Surveyed tracts or parcels of land at request of owner.

Found the SE. cor., S 1/4 cor., SW. cor., W 1/4 cor., NW. cor. and the NE. cor. monuments all in Sec. 31 as per re-estab. notes, recorded in the office of the County Surveyor.

At the NE. cor. of the section found an old 8 in. spike approx. 3 in. deep, this was replaced with a 5/8 in. iron pin and the old spike was re-set along the west side of the cor. the old reference points now are a 3/4 in. iron pin, West 29.60 feet and East 29.60 feet from the corner.

Measured southerly to the SE. cor. of the Sec. and set a 5/8 in. iron pin mid-point, distance which is in close agreement with the survey by Clabby, but disagrees as to where mid-point should be or where the SW. cor. of American Tract should be, by field measurements.

Highway was determined from monuments found.

