

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To remonument and perpetuate the 1/4 Section corner common to Sections 3 and 10 Township 32 South, Range 2 East, W.M.

PROCEDURE:

Found both original bearing trees which are now an 8.9 inch Madrone with scribing "1/4 S" exposed and a 9.8 inch Douglas Fir. I did not expose the scribing in the latter tree. Found an unmarked stone in the position called for the corner and replaced it with a 1 inch by 36 inch galvanized steel pipe driven 30 inches in the ground and topped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped "T 32S R 2E 1/4 Cor. S 3/S10 RS 583 1962", all in 1/8 inch letters and numerals.

The Northwest bearing tree being in poor condition, I marked one additional bearing tree described as follows: from the corner pipe an 18.5 inch Incense Cedar, double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower blaze bears South 35°30' West a distance of 45.2 feet to the face of blaze. Compass variation set at 20°00' East.

Present were Brice Brandt, Kermit Neville and Bud Felker.

December 1962

