



SURVEY NARRATIVE

PURPOSE: To survey and determine the deed corners of instrument number 1999-006038 of the Official Records of Jackson County, Oregon.

PROCEDURE: Utilizing a Trimble R8 GPS receiver and a Nikon DTM 522 total station I tied the set and or found monuments reported on filed survey number 4798 and reported by BLM survey date 12-03-07. I computed my client's deed corners and set, as shown. It is to be noted that the iron rod set on filed survey number 4798 for the CESW 1/64th corner was found to be out of location. The bearing trees reported for this corner were found and were not at the recorded positions. I set a monument to mark the true position. True line was run around boundary, setting 10 inch spikes and 3 foot wood stakes at approximately 100 foot intervals. The true line was blazed and painted flo-red.

LEGEND

- SET 5/8" X 30" REBAR WITH PLASTIC CAP MARKED 'TEMPLIN LS2359'
- ⊕ FD. STANDARD B.L.M. BRASS CAP MONUMENT, PER B.L.M. RECORD
- ⊞ FD. JACKSON COUNTY BRASS CAP MONUMENT, PER JACKSON COUNTY RE-ESTABLISHMENT
- FD. 5/8" REBAR PER F.S. # 4798
- FD. MONUMENT PER F.S. # 6066 (SEE NOTE)
- (>) INDICATES RECORD DATA PER OFFICIAL BLM SURVEY DEC. 3, 2007
- << >> INDICATES RECORD DATA PER FILED SURVEY NUMBER 6066
- INDICATES LINE MARKED WITH 10" SPIKES AND 3' WOOD STAKES AT +-100 FOOT INTERVALS ALONG WITH BLAZING THE TRUE LINE AND PAINTED BLAZES WITH FLO-RED PAINT.

BASIS OF BEARING: NORTH-SOUTH CENTERLINE OF SECTION 32 PER BLM SURVEY AND GPS OBSERVATIONS

****RECEIVED****
 DATE: 8-2-10 BY: [Signature]
 This survey consists of:
 1 sheet(s) Map
 2 page(s) Narrative
JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
 [Signature]
 OREGON
 JULY 26, 1988
 RICHARD G. TEMPLIN
 2359
 MY CERTIFICATE EXPIRES JUNE 30, 2012

FILE: 'LUNDLOT.dwg'
 RICHARD TEMPLIN LAND SURVEYING
 P.O. BOX 1946 899-2032 JACKSONVILLE, OREGON
MAP OF SURVEY
 LOCATED IN
 SE 1/4 OF THE NE 1/4 OF THE SW 1/4 OF SECTION 32,
 T.39S.,R.2W.,W.M., JACKSON COUNTY, OREGON
 FOR: Mr. Ivan Lund
 181 Sterling Crk. Rd.
 Jacksonville, Or. 97530
 DATE: July 21, 2010