

APPROVAL

*Shawn Kampmann*  
 JACKSON COUNTY DEVELOPMENT SERVICES  
 FILE NO. SUB2012-00025  
 DATE 6/28/12

MAP OF SURVEY  
 PROPERTY LINE ADJUSTMENT

LYING SITUATE WITHIN  
 NORTHEAST QUARTER OF SECTION 1  
 TOWNSHIP 36 SOUTH, RANGE 3 WEST, WILLAMETTE MERIDIAN  
 JACKSON COUNTY, OREGON

FOR  
**Ron Anderson**  
 2351 North Shore Drive  
 Delavan, Wisconsin 53115

LEGEND

- 3" BRASS DISK SECTION CORNER IN CONCRETE PER S/N 4886 & 11017 AND JACKSON COUNTY SURVEYOR RE-ESTAB. NOTES (RECOVERED)
- 5/8" IRON PIN w/ YELLOW PLASTIC CAP STAMPED "FRIAR PLS 961" FOR QUARTER SECTION CORNER PER S/N 11017 (RECOVERED)
- QUARTER SECTION CORNER PER S/N 11017, NOT VISITED BY THIS SURVEY (RECORD)
- 5/8" IRON PIN w/ POST PER O.S.H.D. 1950 SAMS VALLEY HIGHWAY 234 GOLD HILL-SNIDER CREEK SECTION MAP DRG. # 7B-3-4 (RECOVERED)
- 5/8"x 24" IRON PIN w/ ORANGE PLASTIC CAP STAMPED "KAMPMANN PLS 2883" (ESTABLISHED)
- PROPERTY LINE
- ADJUSTED PROPERTY LINE
- BOUNDARY LINE
- CENTERLINE
- S/N SURVEY FILE NUMBER, JACKSON COUNTY SURVEYOR
- O.R. OFFICIAL RECORDS, JACKSON COUNTY CLERK
- D.R. DEED RECORDS VOLUME/PAGE, JACKSON COUNTY CLERK
- O.S.H.D. OREGON STATE HIGHWAY DEPARTMENT
- 240+06.35 O.S.H.D. HIGHWAY 234 CENTERLINE STATIONING (TYPICAL)
- 225.00 LT O.S.H.D. HIGHWAY 234 CENTERLINE OFFSET LEFT (TYPICAL)
- ( ) SURVEY RECORD DATA PER S/N 11017 (LARRY FRIAR)
- [ ] SURVEY RECORD DATA PER S/N 4886 (CHARLES HURST)
- { } symbol"/> { } SURVEY RECORD DATA PER O.S.H.D. DRG. NO. 7B-3-4 R/W MAP

CURVE DATA LEGEND

- P.S. POINT OF TANGENT TO SPIRAL
- P.S.C. POINT OF SPIRAL TO CURVE
- P.C.S. POINT OF CURVE TO SPIRAL
- P.T. POINT OF SPIRAL TO TANGENT
- P.O.S. POINT ON SPIRAL
- P.O.C. POINT ON CURVE
- S.A. SPIRAL ANGLE
- S.C. SPIRAL CHORD
- D.O.C. DEGREE OF CURVE (ARC)
- CURVE BY ARC DEFINITION

FLAG	Δ	R	A	T	CHORD
①	38°24'30"	1909.86'	1280.28'	685.24'	N 56°04'15" E - 1256.44'
②	11°14'18"	1949.86'	382.46'	191.85'	N 42°28'46" E - 381.85'
③	17°15'00"	1949.86'	587.04'	295.76'	N 56°43'26" E - 584.83'
④	9°55'50"	1949.86'	337.95'	169.40'	N 70°18'51" E - 337.53'
⑤	5°28'01"	11459.10'	1093.38'	547.10'	N 86°52'10" E - 1092.96'

FLAG	BEARING	DISTANCE
①	N 29°00'34"E	375.85'
②	N 33°04'14"E	158.46'
③	N 35°50'53"E	71.67'
④	N 30°51'58"E	599.34'
⑤	N 45°36'53"E	111.53'
⑥	S 63°55'26"E	127.13'
⑦	N 83°29'24"E	195.15'
⑧	N 78°11'20"E	223.37'
⑨	N 80°22'56"E	499.78'

NOTE: COURSES 1-4 AND 8-9 ARE SPIRAL CHORDS

BASIS OF BEARING

THE BASIS OF BEARING FOR THIS SURVEY IS THE NORTH LINE OF THE NORTHEAST QUARTER OF SECTION 1 IN TOWNSHIP 36 SOUTH, RANGE 3 WEST OF THE WILLAMETTE MERIDIAN, HAVING A RECORD PLAT BEARING OF NORTH 89°58'34" EAST, AS REFERENCED ON SURVEY NO. 11017, ON FILE IN THE OFFICE OF THE JACKSON COUNTY SURVEYOR.

**\*\* RECEIVED \*\***  
 Date 6-28-12 By BB  
 This survey consists of  
1 sheet(s) Map  
0 page(s) Narrative  
 JACKSON COUNTY SURVEYOR

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Shawn Kampmann*  
 OREGON  
 JULY 14, 1998  
 SHAWN KAMPMANN  
 2883 LS

RENEWAL DATE: 6/30/2013

SURVEYED BY:  
**POLARIS LAND SURVEYING LLC**  
 P.O. BOX 459  
 ASHLAND, OREGON 97520  
 (541) 482-5009

DATE: JUNE 6, 2012  
 PROJECT NO. 700-12