

RIGHT OF WAY MONUMENTATION SURVEY

KIRTLAND ROAD REALIGNMENT

TABLE ROCK ROAD TO AVENUE "G"
 LOCATED IN THE SOUTH 1/2 OF SECTION 13,
 T 36 S, R 2 W, W.M., JACKSON COUNTY, OREGON

FD. U.S. ARMY CORPS
 OF ENGINEER'S BRASS
 DISK IN MON. CASE

BASIS OF BEARINGS: CENTERLINE OF AVE. "G" PER S.N. 3700, N 89° 48' 50" W

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR:

JACKSON COUNTY ROADS & PARKS
 200 ANTELOPE ROAD
 WHITE CITY, OREGON 97503

PURPOSE OF SURVEY:

TO SHOW AND MONUMENT THE LOCATION OF
 ADDITIONAL RIGHT OF WAY ACQUIRED FOR
 THIS ROAD PROJECT AND TO SHOW RECOVERED
 MONUMENTS WHICH WERE REMOVED BY
 CONSTRUCTION AND RESET.

PROCEDURE:

A RANDOM TRAVERSE WAS RUN WHICH TIED
 IN THE RECOVERED SURVEY MONUMENTS AND
 GOVERNMENT CORNERS AS SHOWN.

BASIS OF BEARING:

THE CENTERLINE OF AVENUE "G" BEING
 N 89° 48' 50" W, PER RECORDED SURVEY No. 3700.

DATE:

NOVEMBER 30, 2012

RECEIVED
 Date 12-5-12 By [Signature]
 This survey consists of:
1 sheet(s) map
0 page(s) narrative
**JACKSON COUNTY
 SURVEYOR**

**CURVE No. 3
 CURVE RIGHT**

D = 9° 07' 41"
 L = 137.57'
 T = 68.93'
 R = 863.51'
 L.C. = 137.42'
 BRNG. = N 32° 41' 24" E

36 2W 13
 TL 1200

D = 28° 52' 20"
 L = 389.79'
 T = 199.19'
 R = 773.51'
 L.C. = 385.67'
 BRNG. = N 42° 33' 44" E

**INST. 2011-009761
 ROAD (REALIGNED)**

D = 55° 32' 31"
 L = 749.83'
 T = 407.32'
 R = 773.51'
 L.C. = 720.82'
 BRNG. = N 55° 53' 49" E

36 2W 13
 TL 1100

**CURVE No. 2
 CURVE LEFT**

D = 8° 27' 40"
 L = 127.52'
 T = 63.88'
 R = 863.51'
 L.C. = 127.40'
 BRNG. = N 32° 21' 24" E

CURVE No. 1

D = 48° 21' 06"
 L = 206.75'
 T = 109.98'
 R = 245.00'
 L.C. = 200.67'
 BRNG. = N 23° 59' 33" W

- MONUMENTS SET CONSIST OF 5/8" X 24" REBAR AND YELLOW PLASTIC CAP Mkd. "JACKSON CO. ROADS & PARKS" OR AS OTHERWISE NOTED.

JACKSON COUNTY ROADS AND PARKS
 200 ANTELOPE ROAD
 WHITE CITY, OREGON 97503

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

James P. Dickerson

OREGON
 JANUARY 17, 1995
 JAMES P. DICKERSON
 2691

EXP. 12-31-13

