

SE 1/4 SEC 15 T39S R1E WM
JACKSON COUNTY, OREGON

REMONUMENTATION SURVEY NARRATIVE

THE PURPOSE OF THIS SURVEY IS TO REPLACE 4 OF THE RECOVERED SURVEY MONUMENTS AS SHOWN ON JACKSON COUNTY SURVEY NUMBER 20896, THAT WERE DESTROYED BY THE ROADWAY CONSTRUCTION PROJECT KNOWN AS PEACHEY ROAD: WALKER AVE. TO HILLVIEW DR. BY UTILIZING THE HORIZONTAL CONTROL AND RECOVERED MONUMENT POSITIONS PER SAID SURVEY NUMBER 20896, THE DESTROYED MONUMENTS WERE RESET AT THE RECORD COORDINATE VALUES PER SUVEY NUMBER 20896 AND ARE DESCRIBED BELOW.

ALL POINT NUMBERS REFERED TO HEREIN, ARE AS SHOWN ON SAID SURVEY NUMBER 20896.

THIS SURVEY WAS MADE AT THE REQUEST OF THE OREGON DEPARTMENT OF TRANSPORTATION (ODOT), JACKSON COUNTY PUBLIC WORKS AND THE CITY OF ASHLAND.

THE SURVEY EQUIPMENT CONSISTED OF ONE TRIMBLE S6 TOTAL STATION AND ONE TRIMBLE TSC3 DATA COLLECTOR. UNITS ARE INTERNATIONAL FEET.

THIS SURVEY WAS PERFORMED ON OCTOBER 28, 2013.

*S 1005 AND 1019 WERE REPLACED WITH A 5/8"X30" REBAR WITH A BLUE PLASTIC CAP MARKED "OBEC". CAP IS SET DOWN 0.3' FROM THE SURFACE OF THE GROUND.

*1014 WAS REPLACED WITH A 1" BRONZE PLUG MARKED "OBEC", SET FLUSH WITH THE SURFACE OF THE CONCRETE SIDEWALK.

*1015 WAS DESTROYED BY THE CONSTRUCTION OF A BLOCK RETAINING WALL. SUBSEQUENTLY, THE MONUMENT COULD NOT BE RESET IN THE POSISTION IT WAS ORIGINALLY FOUND. A REFERENCE MONUMENT WAS SET ON THE LINE BETWEEN THE ORIGINAL LOCATION OF *1015 AND THE LOCATION OF *1017, BEARING S00°25'00"E, 1.00 FOOT FROM *1015. A 5/8" X 30" REBAR WITH A BLUE PLASTIC CAP MARKED "OBEC" WAS SET FLUSH WITH THE SURFACE OF THE GROUND. POINT COMPUTATIONS RELATED TO THE RETRACED PEACHEY ROAD CENTERLINE AND COORDINATE VALUES PER SAID SURVEY NUMBER 20896 ARE AS FOLLOWS:

SET MONUMENT TABLE FOR REFERENCE MONUMENT TO *1015

OCRS NORTHING	OCRS EASTING	STATION	OFFSET
156270.56	339361.13	"P" 4+13.94	21.02 RT

ALL OTHER FOUND MONUMENTS ON SAID SURVEY NUMBER 20896 WITHIN THE LIMITS OF THE CONSTRUCTION, WERE FOUND TO BE IN PLACE AT THE TIME OF THIS POST CONSTRUCTION SURVEY.

REGISTERED PROFESSIONAL LAND SURVEYOR

11/22/2013

A [Signature]

OREGON
JULY 12, 2005
ARON JAMES CUTSFORTH
65696

RENEWAL: DEC. 31, 2013

** RECEIVED **
DATE 11/21/13 BY D.R.
This survey consists of:
1 sheet(s) Map
0 page(s) Narrative
JACKSON COUNTY SURVEYOR

ODOT REGION 3
KEY NO. 15702
JOB NO. 0019-0100.56
JACKSON COUNTY



Corporate Office: 920 COUNTRY CLUB ROAD, SUITE 100B EUGENE, OREGON 97401-6089, 541-683-6090
2235 MISSION STREET SE, SUITE 100 SALEM, OREGON 97302-1295, 503-589-4100
831 O'HARE PARKWAY MEDFORD, OREGON 97504-4005, 541-774-5590
5000 SW MEADOWS ROAD, SUITE 420 LAKE OSWEGO, OREGON 97035, 503-620-6103
1111 MAIN STREET, SUITE 401 VANCOUVER, WASHINGTON 98660, 360-314-2391

NOVEMBER, 2013
SHEET 1 OF 1