

21421

USDA-FOREST SERVICE

Index **CORNER RECORD (SEARCH)**

File No. N-1 PROJ. NO. BYBEE CORNER SECTION

TOWNS. 30 S RANGE 5E/4E R.D. HIGH CAS. COUNTY JACKSON/KLAMATH GCDB# 100400

MERID. W.M. FOREST RRS STATE OREGON

CORNER DIAGRAM

Obj. Ident. _____

Ident. By _____

Signature _____

PLANE COORDINATE POSTION DATA

State _____ Zone _____

North _____

West _____

Estab. By _____

DESCRIBE CORNER MONUMENT FOUND

FOUND 2-1/2" GLO BRASS CAP ON 2" IRON PIPE, PROJECTING 8" ABOVE THE GROUND, MARKED AS SHOWN

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

DIA	TYPE	BEARS	DIST	FACE/MARKINGS
27"	FIR SNAG	N 20 E	48.3 FT	HEALED SINGLE BLAZE
36"	FIR	S 13-1/4 E	80.4 FT	HEALED SINGLE BLAZE
17"	FIR SNAG	N 4-3/4 W	21.9 FT	PARTIALLY HEALED SINGLE BLAZE
14"	FIR	S 57-1/2 W	22.0 FT	HEALED DOUBLE BLAZE

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

TAKE 6535-970 ROAD TO LOCATION POSTER AT SECTION LINE CROSSING NEAR END, THEN SOUTH 2200 FT TO CORNER

Signature JONATHAN DREW Title LSIT Division LANDS Headquarters SPRINGFIELD SO

REGISTERED PROFESSIONAL LAND SURVEYOR

John Ransom

OREGON
JULY 21, 1992
JOHN C. RANSOM
2561

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

FOUND MONUMENT IN GOOD CONDITION. PUT FLAGGING ON MONUMENT AND GUARD POSTS.

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

MARKED A 17" FIR BEARS, N 55 E - 35.2 FT, MARKED "T30S R5E S18" "BT" ON A DOUBLE BLAZE

MARKED A 19" FIR BEARS, N 7 W - 10.9 FT, MARKED "T30S R4E S13" "BT" ON A DOUBLE BLAZE

PAINTED BT FACES AND 6" RED BAND AT HEAD HEIGHT, NEW NAILS ON EXISTING TAGS, NEW TAGS WHERE NEEDED (BT & ATTENTION)

DONE BY: JONATHAN DREW TITLE LSIT DATE FY 2012 PLS NO./AGENCY/STATE J.RANSOM PLS 2561

Certified Cor. Record Prepared? YES Filed At: KLAMATH/JACKSON DATE _____

REMARKS

MAINTAINED LINE .5 MILES SOUTH OF CORNER TO STANDARD MEASURMENTS TAKEN WITH STAFF COMPASS, 15-3/4° E DECLINATION, AND STEEL TAPE, BEARINGS TO CENTER, DISTANCE TO ALUMINUM NAIL SET AT SIDE CENTER. NEW BT'S INCLUDE 3/4" BRASS WASHER MARKED "LS2561" NAILED FLUSH IN LOWER BLAZE BETWEEN "B" AND "T"