

NW 1/4 SEC 32 T37S R2W WM JACKSON COUNTY, OREGON

REMONUMENTATION SURVEY NARRATIVE

THE PURPOSE OF THIS SURVEY IS TO REPLACE 2 OF THE RECOVERED SURVEY MONUMENTS AS SHOWN ON JACKSON COUNTY SURVEY NUMBER 21002, THAT WERE DESTROYED BY THE ROADWAY CONSTRUCTION PROJECT KNOWN AS FIRST STREET AND MAIN STREET SIDEWALK AND STREETScape. BY UTILIZING THE HORIZONTAL CONTROL AND RECOVERED MONUMENT POSITIONS PER SAID SURVEY NUMBER 21002, THE DESTROYED MONUMENTS WERE RESET AT THE RECORD COORDINATE VALUES PER SAID SURVEY NUMBER 21002 AND ARE DESCRIBED BELOW.

ALL POINT NUMBERS AND COORIDINATE VALUES REFERED TO AND REFERENCED HEREIN, ARE AS SHOWN ON SAID SURVEY NUMBER 21002.

THIS SURVEY WAS MADE AT THE REQUEST OF THE OREGON DEPARTMENT OF TRANSPORTATION (ODOT) AND THE CITY OF JACKSONVILLE.

THE SURVEY EQUIPMENT CONSISTED OF ONE TRIMBLE S6 TOTAL STATION AND ONE TRIMBLE TSC3 CONTROLLER. UNITS ARE INTERNATIONAL FEET.

THIS SURVEY WAS PERFORMED ON MAY 2, 2014.

*1001 WAS REPLACED WITH A 1" BRONZE PLUG MARKED "OBEC", SET FLUSH WITH THE SURFACE OF THE CONCRETE VALLEY GUTTER AT THE RIGHT-OF-WAY CENTERLINE INTERSECTION OF FIRST STREET AND PINE STREET.

*1006 WAS REPLACED WITH A 1" BRONZE PLUG MARKED "OBEC", SET FLUSH IN THE CONCRETE SIDEWALK MARKING THE NORTHWESTERLY CORNER OF THE RIGHT-OF-WAY INTERSECTION OF OREGON STREET AND MAIN STREET.

ALL OTHER FOUND MONUMENTS ON SAID SURVEY NUMBER 21002 WITHIN THE LIMITS OF THE CONSTRUCTION, WERE FOUND TO BE IN PLACE AT THE TIME OF THIS POST CONSTRUCTION SURVEY.

5/21/14

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Aron James Cutforth

OREGON
JULY 12, 2005
ARON JAMES CUTSFORTH
65696

RENEWAL: DEC. 31, 2015

** RECEIVED **

DATE 5/21/14 BY OR

This survey consists of:

__ 1 __ sheet(s) Map

__ 0 __ paget(s) Narrative

JACKSON COUNTY
SURVEYOR

CITY OF JACKSONVILLE &
ODOT REGION 3
KEY NO. 16808
JOB NO. 0019-0100.58
JACKSON COUNTY



Corporate Office: 920 COUNTRY CLUB ROAD, SUITE 100B EUGENE, OREGON 97401-6089, 541-683-6090
2235 MISSION STREET SE, SUITE 100 SALEM, OREGON 97302-1295, 503-589-4100
831 O'HARE PARKWAY MEDFORD, OREGON 97504-4005, 541-774-5590
5000 SW MEADOWS ROAD, SUITE 420 LAKE OSWEGO, OREGON 97035, 503-620-6103
-1111 MAIN STREET, SUITE 401 VANCOUVER, WASHINGTON 98660, 360-314-2391

MAY 21, 2014
SHEET 1 OF 1