## MONUMENT REPLACEMENT SURVEY NARRATIVE

REPLACEMENT OF DESTROYED SURVEY MONUMENTS, PER MAP OF SURVEY FILED SURVEY NUMBER 21256 IN JACKSON COUNTY SURVEYORS OFFICE, BY THIS OFFICE ALONG HOLLY STREET AND GARFIELD STREET, JACKSON COUNTY, OREGON

NORTH 1/2 SECTION 31, TOWNSHIP 37 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN SOUTH 1/2 SECTION 31, TOWNSHIP 37 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN

SURVEY FOR: CITY OF MEDFORD 411 WEST 8TH STREET MEDFORD, OR 97501

SURVEY BY: CITY OF MEDFORD 411 WEST 8TH STREET MEDFORD, OR 97501

DATE OF SURVEY: JULY, 2014



\*\* RECEIVED \*\*

DATE 41614 BY BP

This survey consists of:

o sheet(s) Map

\_\_l\_ page(s) Narrative JACKSON COUNTY SURVEYOR

PURPOSE: TO RE-ESTABLISH THE LOCATION OF 5 OF THE FOUND MONUMENTS DESTROYED BY ROAD CONSTRUCTION. UTILIZING THE CONTROL AND RECOVERED MONUMENT POSITIONS PER SURVEY NUMBER 21256, THE DESTROYED MONUMENTS OUTSIDE EXISTING RIGHT OF WAY WERE RESET AS DESCRIBED BELOW.

EQUIPMENT: ONE TRIMBLE S6 ROBOTIC TOTAL STATION, AND ONE TRIMBLE TSC2 DATA COLLECTOR

PROCEDURE: POINT NUMBERS 113, 114, 120, 121, 122, 509M, 510M AND 534M ARE WITHIN EXISTING RIGHT OF WAY AND NOT RESET.

POINT NUMBERS 150, 154, AND 126 WERE RESET WITH A 5/8"x30" REBAR WITH A 1-1/2" ALUMINUM CAP MARKED CITY OF MEDFORD, AS SEEN IN DETAIL BELOW.


POINT NUMBER 151 WAS RESET WITH A .45 SHELL CASING WITH TACKED BRASS WASHER MARKED C.O.M, SET AT BACK OF SIDEWALK.

POINT NUMBER 503M WAS RESET WITH A LEAD PLUG WITH TACKED BRASS WASHER MARKED C.O.M, SET AT BACK OF CONCRETE WALL.


ALL OTHER FOUND MONUMENTS SHOWN ON SAID SURVEY NUMBER 21256 WITHIN THE LIMITS OF THE CONSTRUCTION, WERE FOUND TO BE IN PLACE AND UNDISTURBED AT THE TIME OF THIS POST CONSTRUCTION MONUMENT REPLACEMENT SURVEY.

NOTE: POINT NUMBER 101 WAS RE-SET BY THE JACKSON COUNTY SURVEYOR'S OFFICE ON AUGUST 7, 2014. SEE THE SEVENTH RE-ESTABLISHMENT AS STAMPED AND SIGNED BY SCOTT FEIN, PLS 83181, DATED AUGUST 28, 2014.

SET MONUMENT DETAIL
5/8" x 30" REBAR WITH A 1-1/2" ALUMINUM CAP
MARKED:







371W31A, 371W31B, 371W31C AND 371W31D

CITY OF MEDFORD - SURVEYING DEPARTMENT

PROJECT NUMBER: P-1561

SHEET 1 OF 1