

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To rehabilitate and perpetuate the 1/4 Section corner common to Section 12, Township 32 South, Range 3 East and Section 7, Township 32 South, Range 4 East, W.M.

PROCEDURE:

Found the original corner monument which is a 14 inch by 15 inch by 18 inch basalt stone set firmly in place and marked "1/4" on the West face. Both original BT's were destroyed by fire many years ago but we found a definite stump hole corresponding to the record location of the Northeast BT. We found no trace of the original Southwest BT. The position of the original monument was further verified by survey South to the Section corner common to Sections 12 and 13, Township 32 South, Range 3 East and Sections 7 and 18, Township 32 South, Range 4E. We found the bearing to be South 00°56' E (Solar) and the distance to be 2644.9 feet.

I used the center of the original stone as the corner point, and after referencing that point, removed the original monument and set in its place a 1 inch by 36 inch galvanized steel pipe driven 30 inches in the ground and capped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

1963  
T 32S  
R 3E R 4E  
12|7  
1/4 COR  
RS 583

The original monument was placed on the North side of the above-described monument.

From the center of the corner pipe a 13.5 inch Douglas Fir, double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower, bears South 66°00' East 39.35 feet; and a 7.5 inch Chinquapin, double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower, bears North 50°30' West 16.75 feet.

Compass variation was set at 20°00' East and distances were measured to face of blaze.

Field work by Robert M. Vincent and Brice L. Brandt.

April 9, 1963



*Robert M. Vincent*

