

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To rehabilitate and perpetuate the 1/4 Section corner common to sections 3 and 2, Township 32 South, Range 3 East, Willamette Meridian.

PROCEDURE:

Found the original Southeast BT which is now a 9 inch Incense Cedar snag with "1/4 S" and "BT" scribed exposed and clearly legible. Also found the original corner monument as described in the official record. This stone was not in place, however, having been disturbed by logging activity and was found approximately 20 feet West (downhill) from its record position. Found no trace of the original Northwest BT.

Set the corner point at the record bearing and distance from the original Southeast BT and monumented with a 1 inch by 36 inch galvanized iron pipe driven 16 inches in the ground and capped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

1963
T 32S R 3E
3 | 2
1/4 COR
RS 583

The original monument was placed on the North side of the above described monument.

From the center of the corner pipe a 16 inch Incense Cedar, double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower, bears North 60°00' East 11.55 feet, and a 16 inch Incense Cedar, double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower, bears South 24°30' West 25.5 feet.

Compass variation was set at 20°00' East and distances were measured to face of blaze.

Field work by Robert M. Vincent and Brice L. Brandt.

April 10, 1963

REGISTERED
OREGON
LAND SURVEYOR

Robert M. Vincent

JULY 9, 1962
ROBERT M. VINCENT
583

RECEIVED
JACKSON
APR 18 1963
COUNTY
SURVEYOR