

Survey No. 2167

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To remonument and perpetuate the 1/4 section corner common to Sections 26 and 27, Township 32 South, Range 1 East, W.M.

PROCEDURE:

Found the original Northwest BT which is now a 17.5 inch Douglas Fir snag. I reopened the lower face and exposed 'BT' scribe. Found no trace of the original Southeast BT or original monument.

At the record bearing and distance from the face of blaze of the original Northwest BT, I set a 1 inch by 36 inch galvanized steel pipe driven 30 inches in the ground and capped with a 1 1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

RS 583
T 32 S R 1E
27|26

1/4 COR
1963

From the corner monument a 35.7 inch Douglas fir single blazed and scribed 'RS 583 BT' bears South 69°00' East 17.4 feet. Also an 18.5 inch Douglas fir single blazed and scribed 'RS 583 BT' bears North 34°00' West 28.4 feet.

Compass variation was set at 20°00' East and distances were measured to face of blaze.

Field work by Robert M. Vincent and Brice L. Brandt.

February 8, 1963

REGISTERED
OREGON
LAND SURVEYOR

Robert M. Vincent

JULY 9, 1962
ROBERT M. VINCENT
583

