

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To rehabilitate and perpetuate the section corner common to Sections 1 and 12, Township 33 South, Range 3 East and Sections 6 and 7, Township 33 South, Range 4 East, W.M.

PROCEDURE:

Found the original Southeast BT which is now an 11 inch White Fir snag, badly decayed but with scribe marks in upper face exposed and plainly legible. Found Chinquapin sprout growth at record position of Northeast BT. Found no trace of the other BT's as this area was burned over in 1910 and has since been heavily logged. Found the original corner monument which is properly oriented and set firmly in the ground. However, this monument falls 1.2 feet North of the corner position as determined by the record bearing and distance from the original Southeast BT. Since the stone is in the edge of a skidroad and there is a definite possibility that it may have been disturbed in logging and replaced in a position other than its original. I set the corner point at the record bearing and distance from the original Southeast BT and monumented with a 1 inch by 36 inch galvanized steel pipe driven 30 inches in the ground and capped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

1963
T 33 S
R 3E R 4E

1/6
12/7
SEC COR
RS 583

I did not disturb the original stone monument and it lies 1.2 feet North of the above-described pipe monument.

I referenced the corner pipe as follows:

A	6 inch	White Fir	bears	North 53°30'	East	28.75 feet
A	5.5 inch	White Fir	bears	South 82°30'	East	13.65 feet
A	5 inch	Douglas Fir	bears	South 59°00'	West	13.5 feet
A	5 inch	Douglas Fir	bears	North 44°00'	West	14.9 feet

All of the trees described above are double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower.

Compass variation was set at 20°00' East and distances were measured to face of blaze.

Field work by Robert M. Vincent and Brice L. Brandt.

April 10, 1963

REGISTERED
OREGON
LAND SURVEYOR

Robert M. Vincent
JULY 9, 1962
ROBERT M. VINCENT
583

RECEIVED
JACKSON
APR 18 1963
COUNTY
SURVEYOR