

**MAP OF SURVEY**  
 FOR  
**CELESHA GORSKI**  
 SITUATED IN  
**THE SOUTHEAST QUARTER OF SECTION 33,**  
**TOWNSHIP 36 SOUTH, RANGE 2 WEST,**  
**WILLAMETTE MERIDIAN,**  
**JACKSON COUNTY, OREGON**

HOFFBUHR & ASSOCIATES, INC.  
 880 GOLF VIEW DRIVE, SUITE 201  
 MEDFORD, OREGON 97504  
 (541)779-4641

BY: DARRELL L. HUCK PLS No. 2023  
 SCALE: 1 Inch = 100' April 17, 2015  
 BASIS OF BEARING: SURVEY NO. 3374

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
 OREGON REVISED STATUTES

PURPOSE: To survey and monument the boundary of that property described in Instrument No. 2014-003165 of the Official Records of Jackson County, Oregon

PROCEDURE: The boundary of the property now being surveyed was previously determined by surveyor Mark Boyden per filed Survey No. 3374. Monuments, as found, from that survey were tied and held for control for this survey. I reviewed Boyden's procedure for establishing the property boundary and I followed the precedent as set forth by him. As Boyden has described in his narrative, the west boundary was established 13.46 chains westerly from and parallel with, the east boundary of DLC No. 61, to agree with the adjoining tract description per deed Volume 419, Page 156. It should be noted that Survey No. 19484 used different procedure to determine the location of the west line, which overlaps the boundary as determined by Boyden. I computed the property boundary according to the boundary as set forth by Boyden's Survey No. 3374 and set monuments, as shown.

Equipment used: Trimble S6 Robotic instrument.

**LEGEND**

- Found 5/8" Iron rebar per Survey No. 3374.
- ▲ Found 5/8" Iron rebar per Survey No. 19484.
- Found 3/4" I.D. Iron pipe - not of record, origin unknown.
- Set 5/8"x24" Iron rebar with plastic cap stamped "D. Huck LS 2023".
- x- Fence line.

WIT. Witness monument.  
 D/R Official Records, Jackson County, Oregon

**\*\*RECEIVED\*\***  
 Date 6/4/15 By PB  
 This survey consists of:  
1 sheet(s) Map  
2 pages(s) Narrative  
**JACKSON COUNTY**  
**SURVEYOR**

**REGISTERED**  
**PROFESSIONAL**  
**LAND SURVEYOR**  
*Darrell L. Huck*  
**OREGON**  
 FEBRUARY 4, 1989  
**DARRELL L. HUCK**  
 2023  
 Expires 6/30/2015

(15006MOS.DWG)

