

MAP OF SURVEY

LOCATED IN:  
THE SW 1/4 OF SECTION 20, T33S, R1W, WM.  
JACKSON COUNTY, OREGON

FOR:  
GREG LILES LOGGING  
4580 CRATER LAKE AVE.  
MEDFORD, OREGON 97504



SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.50  
OREGON REVISED STATUTES

PURPOSE: TO SURVEY, MONUMENT AND PREPARE A MAP OF  
SURVEY OF PROPERTY GRANTED TO GREG LILES  
PER INSTRUMENT NO. 2009-013126, J.C.D.R.

PROCEDURE: UTILIZING FOUND MONUMENTS AND INFORMATION PER  
FILED SURVEYS NO. 12068 AND 13589 FOR CONTROL, I  
RAN A TRAVERSE TO TIE AND VERIFY FOUND MONUMENTS.  
I THEN COMPUTED THE BOUNDARIES OF CLIENT'S PROPERTY  
AND SET MONUMENTS AS SHOWN HEREON. AN ELECTRONIC  
TOTAL STATION WAS USED FOR ALL MEASUREMENTS. THE  
NORTH, SOUTH AND WEST BOUNDARIES WERE FLAGGED AND  
BLAZED. THE EASTERN BOUNDARY AND 30' FLAG WERE NOT  
BLAZED OR FLAGGED.

SURVEY BY:

MCAHAN SURVEYING, LLC  
DOUGLAS C. MCAHAN LS1913  
40853 HWY 62 PROSPECT, OR. 97536  
PHONE NO.: 541-261-0648

DATE: JUNE 30, 2015 SCALE: 1" = 200'  
BASIS OF BEARING: FILED SURVEY NO. 12068

- = FOUND 5/8" STEEL PIN WITH PLASTIC CAP  
MARKED "D.W. EDWARDS-LS741" PER FILED  
SURVEYS NO. 12068 AND 13589.
- = SET 5/8"x24" REBAR WITH PLASTIC YELLOW  
CAP STAMPED "MCAHAN SURVEYING, LLC"

J.C.D.R. = JACKSON COUNTY DEED RECORDS  
S/N = FILED SURVEY NUMBER  
{ } = COMPUTED PER S/N 13589  
[ ] = PER S/N 13589

