

Survey No. 2210

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250, OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To rehabilitate & perpetuate the $\frac{1}{4}$ corner to Secs 3 & 10 T33S R1E.

PROCEDURE:

Found the original monument which was a basalt stone 13 inches by 16 inches by 10 inches set firmly in place and plainly marked "1/4" on North face. Also found the Northeast BT which is now a 20 inch Ponderosa Pine in good condition. I opened the lower face in this tree sufficiently to expose scribe markings. The Southeast BT is now a 6 inch Black Oak alive, but badly decayed and with markings obliterated except for a piece of callus tissue showing reversed scribe marks which I had nailed to the side of the tree many years ago.

I used the center of the original stone as the corner point and, after referencing that point, removed the stone and set in its place a 1 inch by 36 inch galvanized steel pipe driven 10 inches in the ground and surrounded with a mound of stone which includes the original monument. The pipe monument is capped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

1963

T 33 S R 1 E

$\frac{3}{10}$

1/4 COR
RS 583

From the center of this corner monument, the original Northeast BT, as described above, bears North $60^{\circ}00'$ East 30.00 feet; the original Southeast BT, as described above, bears South $60^{\circ}30'$ East 19.8 feet; a 7.5 inch Incense Cedar double blazed and scribed "R.S. 583" in the upper blaze and "BT" in the lower, bears South $18^{\circ}30'$ East 15.2 feet to face of lower blaze.

Compass variation set at $20^{\circ}00'$ East.

Field work by Robert M. Vincent and John L. Gartman.

May 20, 1963

