



LEGEND/NOTES:

- △ SET 5/8" x 24" IRON REBAR W/BLUE PLASTIC CAP MARKED "T. ZEUTZIUS PLS 56123", SURVEY CONTROL POINT
- ⊗ SET 60D SPIKE WITH 1-1/4" BRASS WASHER MARKED "PLS 56123" IN ASPHALT, SURVEY CONTROL POINT
- C.P. # CONTROL POINT NUMBER

NARRATIVE:

THE PURPOSE OF THIS SURVEY IS TO ESTABLISH CONTROL FOR THE JACKSON COUNTY ROAD DEPARTMENT ALONG A PORTION OF NORTH RIVER ROAD FOR THE PLANNING AND DESIGN OF A MULTIPURPOSE PATH. CONTROL POINTS WERE SET AS SHOWN HEREON.

THE FIELD WORK FOR THIS SURVEY WAS EXECUTED WITH A TRIMBLE R8 GPS RECEIVER AND TRIMBLE TSC3 DATA COLLECTOR CONNECTED TO THE OREGON REALTIME GEODETIC NETWORK (ORGN), NAD 83(2011)(EPOCH 2010.00). CONTROL POINT MEASUREMENTS WERE SURVEYED UTILIZING THE "DOUBLE TIE" METHOD SPECIFIED IN THE OREGON DEPARTMENT OF TRANSPORTATION "SURVEY POLICY AND PROCEDURE MANUAL" DATED AUGUST 14, 2015.

COORDINATES ARE BASED UPON A LOCAL SURVEY CONTROL COORDINATE SYSTEM.

FILED
Date 8/24/17 By PB
This Survey Consists Of:
1 sheet(s) Map
0 page(s) Narrative
JACKSON COUNTY SURVEYOR

Peter D. Allen Land Surveying
321 N.W. "A" Street
Grants Pass, Oregon 97526
541-476-4502

REGISTERED PROFESSIONAL LAND SURVEYOR
TODD J. ZEUTZIUS
RENEWAL: JUNE 30, 2018

MAP OF SURVEY OF CONTROL POINTS SET FOR NORTH RIVER ROAD MULTIPURPOSE PATH
LOCATED IN
Township 36 South, Ranges 3 & 4 West, W.M. JACKSON COUNTY, OREGON
SURVEY FOR
Jackson County Road Dept. White City, Oregon

PROJECT NUMBER: 2017-047-961
DRAWING FILE: JacksonCo-NRiverRd.dwg
DRAWING SCALE: 1" = 400'
DATE: August 18, 2017
SHEET: 1 OF 1 (tz)

THIS PLAT WAS PREPARED WITH A HEWLETT-PACKARD (HP) DESIGNJET 500 USING HP NO. C4844A INK/ET INK ON CONTINENTAL IMAGING NO. JPC4M2 POLYESTER FILM.