

2250

Survey For
E.M. HAYS

Located in Sec. 14, T. 36 S., R. 1 W., W.M.

By: Mark E. Boyden

April, 1963

(J.C.D.R. Vol. 337, Page 41)

SCALE : 1" = 200'

N

80.00'

Fd. 1-1/2" iron pipe

1027.67'

N 0°02'25" W

REGISTERED
OREGON
LAND SURVEYOR

Mark E. Boyden

NOVEMBER 9 1951
MARK E. BOYDEN
281

C See Recorded Survey No. 169 J

1/4 Section Corner

Fd. U.S.A.E. conc. mon.

with bronze disk

15 14

S 89°57'20"E

1328.27'

Set 1" iron pipe

2250

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: E. M. Hays
c/o A. T. Wattenburg
Rt. 1, Box 104
Eagle Point, Oregon

LOCATION: Northwest 1/4 of Section 14, Township 36 South,
Range 1 West, Willamette Meridian.

PURPOSE: To monument the East boundary and the
Easterly portion of the South boundary of that
tract described in Volume 534, Page 161 of
the Deed Records of Jackson County, Oregon.

PROCEDURE:

The description for this tract described in
said Volume 534, Page 161 was prepared by this office
from records derived from Recorded Survey No. 169. It
was the intention of this office description, that the
portion of the South boundary which lies within Section 14
would not necessarily follow the "East-West" centerline
of Section 14, but be controlled by bearings established
on Recorded Survey No. 169.

Ran traverse from the officially renewed Quarter
corner common to Sections 14 and 15, being a concrete
monument with bronze disk, Easterly and Northerly to the
1-1/2" iron pipe set for a witness corner for the Southeast
corner of the parcel surveyed on Recorded Survey No. 169.

A reasonable closure was obtained, and the
boundaries were then monumented, and bearings and distances
reported to conform with said previous survey No. 169.

May 1963

