

MONUMENT REPLACEMENT SURVEY NARRATIVE

LOCATED IN THE NORTHEAST 1/4 OF SECTION 25, TOWNSHIP 37 SOUTH, RANGE 2 WEST, AND THE NORTHWEST 1/4 OF SECTION 30, TOWNSHIP 37 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN IN THE CITY OF MEDFORD, JACKSON COUNTY, OREGON

SURVEY FOR AND BY:
CITY OF MEDFORD
411 WEST 8TH STREET
MEDFORD, OR 97501

DATE OF SURVEY: OCTOBER, 2018

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JANUARY 9, 2007
JON M. PROUD
77652


EXPIRES DECEMBER 31, 2018

** RECEIVED **
DATE 12/11/18 BY PB
This survey consists of:
0 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR

PURPOSE: TO REPLACE DESTROYED SURVEY MONUMENTS ALONG 6TH STREET BETWEEN NORTH FIR STREET AND NORTH IVY STREET, PER MAP OF SURVEY NUMBER 22555 FILED IN THE JACKSON COUNTY SURVEYOR'S OFFICE. MONUMENTS WERE DESTROYED DURING THE 6TH STREET STORM DRAIN REPLACEMENT PROJECT. UTILIZING EXISTING PROJECT CONTROL AND RECOVERED MONUMENT POSITIONS PER SAID SURVEY 22555, THE DESTROYED MONUMENTS WERE RESET AS DESCRIBED BELOW.

PROCEDURE: UTILIZING A TRIMBLE S6 ROBOTIC TOTAL STATION, REDUNDANT MEASUREMENTS WERE MADE TO POINT NUMBERS 514M, 542M, AND THE CENTERLINE INTERSECTION OF NORTH FIR STREET AND 6TH STREET PER SURVEY 22555. THESE POINTS WERE RESET WITH A 5/8" REBAR WITH AN ALUMINUM CAP MARKED "CITY OF MEDFORD" AS SHOWN IN DETAIL BELOW. CAP IS SET FLUSH IN ASPHALT.

SET MONUMENT DETAIL
5/8" REBAR WITH A 1-1/2" ALUMINUM
CAP MARKED:



372W25A AND 371W30B