

**FILED**  
 Date 6/4/19 By PB  
 This Survey Consist Of:  
 1 sheet(s) Map  
 0 page(s) Narrative  
**JACKSON COUNTY SURVEYOR**

**MAP OF SURVEY FOR WILLIAM HUNTER**

14209 Racine Circle  
 Nimshew, CA. 95954

LOCATED IN:  
 THE N.W. 1/4 SEC. 34, T.34S., R.4W., W.M.  
 JACKSON COUNTY, OREGON

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
 OREGON REVISED STATUTES

PURPOSE: To survey and monument property described in Instrument No. 2018-008736 of the Official Records of Jackson County, Oregon

PROCEDURE: The property being surveyed is located in the east 1/2 of the Northwest 1/4 of the Northwest 1/4 of Section 34. The location of the boundary of this East 1/2 has been previously determined per surveys No. 13763 and 19807. The northerly portion of the property was monumented per survey No. 13763 and monuments as found per that survey were located and held for control. The location of the Northwest 1/16 corner has been monumented per survey No. 19807 which was tied and accepted for control. Utilizing information taken from the filed surveys No. 13763 and 19807, the location of the east 1/2 of the Northwest 1/4 of the Northwest 1/4 was computed, which controls the location of the southwesterly and south lines, which were then computed according to deed description and monuments were set as shown. Equipment used: Trimble S6 Robotic instrument.

HOFFBUHR & ASSOCIATES, INC.  
 880 GOLF VIEW DRIVE, SUITE 201  
 MEDFORD, OREGON 97504  
 (541)779-4641

BY: DARRELL L. HUCK PLS No. 2023  
 SCALE: 1 inch = 100' APRIL 10, 2019  
 BASIS OF BEARING: SURVEY NO. 13763

- = Set 5/8"x24" iron reinforcing pin with plastic cap stamped "D. Huck LS 2023".
- = Found 5/8" iron pin per Survey No. 13763, unless noted otherwise
- △ = Computed point
- O.R. = Official Records, Jackson County, Oregon
- S/N = Survey Number
- [ - ] = Record per Survey Number 13763
- { - } = Record per Survey Number 19807

**CURVE TABLE**

No.	Delta	Radius	Arc	Chord	Chord Brg
C1	6°30'17"	225.00	25.54'	25.53'	S11°23'51"E
		[225.00]	[25.53']	[25.51']	[S11°30'09"E]
C2	6°23'29"	225.00	25.09'	25.10'	S04°56'58"E
		[225.00]	[25.11']	[25.10']	[S05°03'22"E]

**REGISTERED PROFESSIONAL LAND SURVEYOR**

*Darrell L. Huck*

OREGON  
 FEBRUARY 4, 1983  
 DARRELL L. HUCK  
 2023

Expires 6/30/2019

(19037MOS.DWG)

