



361w11ac 201

**Map of Survey**  
**Eagle Crest Overlook Subdivision, Lot 2**  
 Located In:  
 SW1/4, NE1/4, Section 11, Township 36 South, Range 1 West, W.M.  
 City of Eagle Point, Jackson County, Oregon

**\*\* RECEIVED \*\***  
 DATE 10/1/20 BY [Signature]  
 This survey consists of:  
 1 sheet(s) Map  
 0 page(s) Narrative  
 JACKSON COUNTY SURVEYOR

Survey Narrative:  
 Purpose:  
 Re-set the lot corner common to Lot 2, Lot 15 and Lot 3 of Eagle Crest Overlook Subdivision, Phase 1, 2 and 3.

Procedure:  
 Utilizing the control established by this firm for Eagle Crest Overlook Subdivision, the missing property corner common to Lot 2, Lot 15 and Lot 3 was re-set in the record position. Ties to existing lot corners were used to validate the re-set lot corner position.

Date of Survey: August 31, 2020.

Equipment used: Trimble S6 Total Station

R= Curve Table:

No.	Length	Radius	Delta	Long Chord
C32	90.33'	608.96'	8°29'55"	S22°50'43"E, 90.24'

**LEGEND**

- Found 5/8" Rebar per Filed Survey 22377
- Set 5/8" x 24" Rebar w/Cap Marked "PARIANI PLS51382"
- R= Record data per Filed Survey 22377

**Survey For:**

J and N Investments, LLC,  
 an Oregon limited liability company  
 533 Brookside Lane  
 Central Point, OR 97502

**Survey By:**

Pariani Land Surveying  
 P.O. Box 551  
 Shady Cove, OR 97539

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR  
  
 OREGON  
 July 13, 1999  
 JOHN R. PARIANI  
 #51382

Renews: December 31, 2020

**Pariani Land Surveying**

P.O. Box 551  
 Shady Cove, OR 97539  
 541-890-1131

Date: Sept. 21, 2020	Scale: 1" = 50'	Job No.: 2015-270	Sheet: 1 of 1
-------------------------	--------------------	----------------------	------------------