

MAP OF SURVEY

SURVEY FOR:
 Dallas L. Hansen and
 Theodore Cooper
 20990 Antioch Road
 White City, OR. 97503

SURVEY BY:
 Kaiser Surveying
 2178 Butte Falls Hwy.
 Eagle Point, OR. 97524

LOCATION:
 North Half of Section 22,
 T.34S.,R.2W., W.M.,
 Jackson County, Oregon

DATE:
 April 22, 2021

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

PURPOSE: Boundary survey of the West boundary of the client's property described in Instrument No. 2014-010888 O.R..

PROCEDURE: Equipment used on survey was a Nikon DTM-522 Total Station. The boundaries of the subject property are described by aliquot parts being the North Half of the Northwest Quarter and the Northwest Quarter of the Northeast Quarter of Section 22 in Township 34 South, Range 2 West of the Willamette Meridian. Survey ties were made to the Northwest Section corner and the West Quarter corner of said Section 22. The North 1/16 corner, being the Southwest corner of the subject property was then computed and was found to fall in a creek. Monuments were set on the property line with a reference monument set to the said South 1/16 corner as shown. The property line was also marked with 36" lath.

LEGEND

- ⊙ = Found B.L.M. Monument as Indicated
- = Set 5/8" x 30" Rebar with Orange Plastic Cap marked "B KAISER LS 52923"
- x-x- = Fence
- S.N. = Filed Survey Number
County Surveyors Office
- R.M. = Reference Monument
- () = Record/S.N. 19839

**** RECEIVED ****
 Date 5/4/21 By DR
 This survey consists of:
1 sheet(s) Map
0 page(s) Narrative
JACKSON COUNTY SURVEYOR

REGISTERED
**PROFESSIONAL
 LAND SURVEYOR**

Bary D. Kaiser
OREGON
 JULY 15, 2003
 BARY D. KAISER
 No. 52923
 EXP. 6-30-21

Map No. 342W22 Tax Lot No. 200

