

CORNER INVESTIGATION REPORT

23380

FS INDEX ID: D-1/2-10

CORNER: C-S-SW 1/64 GCDB ID: 320610 DATE: 12/16/2020
TOWNSHIP: 40S STATE: OREGON
RANGE: 3W COUNTY: JACKSON
SECTION: 4 FOREST: ROGUE RIVER-SISKIYOU NF
MERIDIAN: WILLAMETTE DISTRICT: SISKIYOU MOUNTAINS RD
NFSL PROPERTY BOUNDARY CORNER?: YES NO

HISTORY OF VISITATIONS:

LINE(S) POSTED:
MAINTAINED: WEST-2021
GUARD POST(S): WEST NORTH
CORNER HISTORY:
 SET DURING FILED SURVEY 8682, BY KURT C. WEAVER

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

Jason M. Martin
**OREGON
 MAY 8, 2012
 JASON M. MARTIN
 54729**

RENEWS: 1-1-2023

MONUMENT FOUND/SET:
 2 1/2" BRASS CAP ON 2 1/2" PIPE, APPROX. 0.5' EXPOSED, NO STONES,
 GOOD CONDITION

RECORD MEASUREMENTS:

BEARS S21°18'E, 13.0'
 BEARS S76°19'W, 30.9'

RECORD CORNER ACCESSORIES:
 PER FILED SURVEY 8682
 8" DIA FIR (NOW 10") HEALED BLAZES
 8" DIA OAK (NOW 11") HEALED BLAZES

FILED
 Date 6/25/21 By PB
 This Survey Consist Of:
0 sheet(s) Map
1 page(s) Narrative
**JACKSON COUNTY
 SURVEYOR**

METHOD OF MEASUREMENT:

NEW CORNER ACCESSORIES:
 NO NEW ACCESSORIES ESTABLISHED

CORNER MAINTENANCE/OTHER INFO:
 CLEAR BRUSH FROM AROUND MONUMENT & TO BT'S. BT FACES & A 6" BAND AT
 HEAD HEIGHT PAINTED RED. ADD NEW NAILS TO BT TAGS & ADD NEW TAGS
 WHERE NEEDED. MONUMENT SIZES ARE OUTSIDE DIAMETER & BT DIAMETERS
 ARE AT BREAST HEIGHT.

GEODETIC COORDINATES:
LATITUDE: N 42°06'52.7"
LONGITUDE: W123°04'03.5"
ELLIPSOID HEIGHT: ~1901
DATUM: WGS-84
SOURCE: CONSUMER GRADE G.P.S.
DATE OF INVESTIGATION: 1/19/21
REPORT BY: J. MARTIN

DOCUMENTS ON FILE AT:

FIELD CREW: DENNIS H. MORTON, PARTY CHIEF
 TOM MILSTEAD, FIELD TECH

THIS DOCUMENT FILED IN CS OFFICE:
OTHER DOCUMENT FILED WITH CS:

