

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250, OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To rehabilitate and perpetuate the 1/4 Section corner common to Sections 21 and 22, Township 33 South, Range 1 East, W.M.

PROCEDURE:

Found the reversed "1/4" scribe in callus tissue of badly decayed remains of original Northeast bearing tree which is a down and badly deteriorated 18 inch Black Oak. Found no trace of the original Southwest bearing tree.

At the record bearing and distance from the base of the original Northeast BT, I set a 1 inch by 36 inch galvanized steel pipe driven 30 inches in the ground and capped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

1963
T 33 S R 1E
21/22
1/4 COR
RS 583

From this monument a 7.5 inch Douglas fir bears South 86° 45' West 16.04 Feet and a 9.5 inch Douglas fir bears North 43° 00' East 42.0 feet. Both trees are double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower. Distances were measured to the face of the lower blaze.

Compass variation set at 20° 00' East.

Field work by Robert M. Vincent and John Flanagan.

October 29, 1963

REGISTERED
OREGON
LAND SURVEYOR

Robert M. Vincent

JULY 9, 1962
ROBERT M. VINCENT
583

RECEIVED
JACKSON
NOV 05 1963
COUNTY
SURVEYOR