

# CORNER INVESTIGATION REPORT

FS INDEX ID: E-9

CORNER: SOUTHEAST      GCDB ID: 300600      DATE: 1/29/21  
TOWNSHIP: 40S      STATE: OREGON  
RANGE: 3W      COUNTY: JACKSON  
SECTION: 5      FOREST: ROGUE RIVER-SISKIYOU NF  
MERIDIAN: WILLAMETTE      DISTRICT: SISKIYOU MOUNTAINS RD  
NFSL PROPERTY BOUNDARY CORNER?:  YES  NO

HISTORY OF VISITATIONS:

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*Jason M. Martin*  
**OREGON  
MAY 8, 2012  
JASON M. MARTIN  
54729**

RENEWS: 1-1-2023

RECORD MEASUREMENTS:

BEARS N62°09'W, 22.5'  
 BEARS N32°47'W, 4.7'  
 BEARS N25°12'W, 23.9'

BEARS N47°16'E, 26.5'  
 BEARS N72°02'E, 8.5'  
 BEARS S49°30'E, 15.2'  
 BEARS S34°08'E, 1.9'  
 BEARS S07°50'W, 24.3'  
 BEARS S60°14'W, 22.7'

METHOD OF MEASUREMENT:

LINE(S) POSTED:

MAINTAINED: WEST-2021 NORTH-2021

GUARD POST(S): WEST NORTH

CORNER HISTORY:

VISITED BY JACKSON COUNTY SURVEYOR, FIRST RE-ESTABLISHMENT, 1960  
 MONUMENT SET BY BLM IN 1964, BY JOSEPH S. GAWRON  
 VISITED DURING FILED SURVEY 8683, BY KURT C. WEAVER

MONUMENT FOUND/SET:

3 1/2" BRASS CAP ON 2 1/2" PIPE, APPROX 0.5' EXPOSED, NEXT TO ONE STONE  
 WITH 4 HASH MARKS ON 2 SIDES, MONUMENT HAS SLIGHT MOVEMENT WHEN  
 GRABBED, OTHERWISE GOOD CONDITION

RECORD CORNER ACCESSORIES:

- PER FILED SURVEY 8683
- 16" DIA FIR (NOW 23") HEALED BLAZE
- 13" DIA FIR (NOW 17") HEALED BLAZES
- 16" DIA OAK STUMP ROTTED BLAZE
- 9" DIA OAK SNAG NO EVIDENCE
- 12" DIA FIR (NOW 16.5") HEALED BLAZE
- 15" DIA FIR (NOW 18") HEALED BLAZES
- 8" DIA FIR (NOW 9") HEALED BLAZE
- 10" DIA FIR (NOW 12.5") HEALED BLAZES
- 11" DIA FIR (NOW 17") HEALED BLAZES
- 8" DIA FIR (NOW 12") HEALED BLAZES

**FILED**  
 Date 7/7/21 By PB  
 This Survey Consist Of:  
~~0~~ sheet(s) Map  
 1 page(s) Narrative  
**JACKSON COUNTY  
SURVEYOR**

NEW CORNER ACCESSORIES:

NO NEW ACCESSORIES ESTABLISHED

CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT & TO BT'S. BT FACES & A 6" BAND AT  
 HEAD HEIGHT PAINTED RED. ADD NEW NAILS TO BT TAGS & ADD NEW TAGS  
 WHERE NEEDED. MONUMENT SIZES ARE OUTSIDE DIAMETER & BT DIAMETERS  
 ARE AT BREAST HEIGHT.

GEODETIC COORDINATES:

LATITUDE: N 42°06'45.9"  
 LONGITUDE: W 123°04'19.2"  
 ELLIPSOID HEIGHT: ~1980  
 DATUM: WGS-84

DOCUMENTS ON FILE AT:

SOURCE: CONSUMER GRADE G.P.S.

DATE OF INVESTIGATION: 1/13/21

REPORT BY: JASON MARTIN

FIELD CREW: DENNIS H. MORTON, PARTY CHIEF  
 TOM MILSTEAD, FIELD TECH  
 RYAN BEIL, FIELD TECH

THIS DOCUMENT FILED IN CS OFFICE:

OTHER DOCUMENT FILED WITH CS:

CAP DIAGRAM:

