

# CORNER INVESTIGATION REPORT

FS INDEX ID: H 3/4, 4 3/4

CORNER: W.C. SE-SE-SE 1/256 GCDB ID: 175105 DATE: 4/7/2021  
TOWNSHIP: 40S STATE: OREGON  
RANGE: 3W COUNTY: JACKSON  
SECTION: 7 FOREST: ROGUE RIVER-SISKIYOU NF  
MERIDIAN: WILLAMETTE DISTRICT: SISKIYOU MOUNTAINS RD  
NFSL PROPERTY BOUNDARY CORNER?:  YES  NO

HISTORY OF VISITATIONS:

LINE(S) POSTED:  
MAINTAINED: WEST-2021  
GUARD POST(S): EAST WEST

CORNER HISTORY:  
SET ON FILED SURVEY 8436, BY MALCOLM N. CLARK

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Jason M. Martin*  
OREGON  
MAY 8, 2012  
JASON M. MARTIN  
54729

RENEWS: 1-1-2023

MONUMENT FOUND/SET:  
FOUND A 2 1/2" BRASS CAP ON 2 1/2" PIPE, IN SMALL PILE OF STONES, APPROX. 1.0' EXPOSED, SET FIRM, GOOD CONDITION

RECORD MEASUREMENTS:

RECORD CORNER ACCESSORIES:  
PER FILED SURVEY 8439:

- 18" DIA OAK (NOW 22.5" ), HEALED BLAZES
- 12" DIA OAK ( NOW 18" ), HEALED BLAZES

- BEARS N53°E, 108.1'
- BEARS N40°45'W, 26.6'

**FILED**  
Date 7/7/21 By PB  
This Survey Consist Of:  
2 sheet(s) Map  
1 page(s) Narrative  
**JACKSON COUNTY  
SURVEYOR**

METHOD OF MEASUREMENT:

NEW CORNER ACCESSORIES:  
NO NEW ACCESSORIES ESTABLISHED

CORNER MAINTENANCE/OTHER INFO:  
CLEAR BRUSH FROM AROUND MONUMENT & TO BT'S. BT FACES & A 6" BAND AT HEAD HEIGHT PAINTED RED. ADD NEW NAILS TO BT TAGS & ADD NEW TAGS WHERE NEEDED. MONUMENT SIZES ARE OUTSIDE DIAMETER & BT DIAMETERS ARE AT BREAST HEIGHT.

CAP DIAGRAM:



GEODETIC COORDINATES:  
LATITUDE: N 42°05'56.8"  
LONGITUDE: W 123°05'48.8"  
ELLIPSOID HEIGHT: ~1701'  
DATUM: WGS-84  
SOURCE: CONSUMER GRADE G.P.S.  
DATE OF INVESTIGATION: 3/24/21  
REPORT BY: JASON MARTIN

DOCUMENTS ON FILE AT:

FIELD CREW: DENNIS H. MORTON, PARTY CHIEF  
TOM MILSTEAD, FIELD TECH

THIS DOCUMENT FILED IN CS OFFICE:  
OTHER DOCUMENT FILED WITH CS: