SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To rehabilitate and perpetuate the Section corner common to Sections 21, 22, 27 and 28, Township 33 South, Range 1 East, W.M.

PROCEDURE:

Found the remains of all four of the original BT's, all of which are in poor condition:

The original Northeast BT is now a live 16 inch Black Oak, hollow in the center, with old faces visible but all scribing obliterated by decay.

The original Southeast BT is now dead and down White Oak with outline of old faces apparent but all scribing obliterated by decay.

The original Southwest BT is now a 13 inch White Oak, alive but in poor condition. I reopened the faces and identified portions of the old scribing.

The original Northwest BT is now a down White Oak snag with "BT" scribe intact.

At the corner point, I set a 1 inch by 36 inch galvanized steel pipe driven 18 inches in the ground to bedrock and capped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

1963 T 33 S R 1 E

21 22 28 27

SEC COR

From this monument I marked new BT's as follows:

A 9.5 inch Douglas fir, double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower, bears North 35° 30' East 18.9 feet to face of lower blaze.

A 9.0 inch Douglas fir, double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower, bears South 69° 00' West 17.8 feet to face of upper blaze.

A 15.0 inch Douglas fir, double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower, bears South 32° 15' East 13.9 feet to face of upper blaze.

An 11.5 inch Douglas fir single blazed and scribed "RS 583 BT" bears North 39° 15' West 6.03 feet to face of blaze.

Compass variation set at 20° 00' East

