



10 11
 N 1/16 Cor.
 U.S. Govt 1961 tablet
 in 1 1/2" pipe
 T 36 S. R. 3 W.

REGISTERED
 OREGON
 LAND SURVEYOR

L. N. Dow

MAY 6, 1949
 L. N. DOW
 251

Survey for Volo Tolman,
 In S 1/2 of NE 1/4 S 10 T. 36 S. R. 3 W. Jackson County, Oregon.
 Dec. 19, 1963 Bearings from Solar Obs.
 All bars are 5/8" x 24" x 3/32" driven to ± 2" of ground surface
 All lines are interior - no previous record

RECEIVED
 JACKSON
 JAN 03 1964
 COUNTY
 SURVEYOR

Written narrative to accompany plat for Survey NO. 2374

Survey located in South 1/2 of Northeast 1/4 of Sec. 10,
Township 36 South, Range 3 West, Jackson County, Oregon.

Survey for Vola Tolman, R 2 Box 360A Gold Hill, Oregon.

Purpose to stake out 5 Acres along lines as requested:

Procedure:

The 1/4 Section corner on the north bank of the Rogue River was inspected and found to be a brass tablet in 1 1/2" pipe with several B.L.M. Bearing tree Tags, following the cut line to the north of this 1/4 corner we find a 1/16 Section corner, a brass in pipe (1 1/2") as called for in the deed record, from this point we ran a tie line westerly, and after taking solar observations (2) we corrected and set a 5/8" bar at a point 1145.60 feet West and 30.00 feet south of the above 1/ 16 corner for the point of beginning, We then traversed the tract and set 5/8" bars 24" and 30" long depending on the depth of rock, these bars set to a plus or minus 2" from ground surface,

