

Survey No. 2408

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To rereference the North 1/16 corner, Sections 28 and 27,
Township 32 South, Range 3 East, W. M.

PROCEDURE: Found the corner pipe which is a 1" x 7/8" pipe projecting 3 inches above ground level, also the stub of one C. S. BT which had blown down but returned to upright position after top was bucked off in salvage logging. From the corner pipe, this C. S. BT now bears North 12° East 18.5 feet to face of healed blaze.

New BT's are as follow:

A 20.4 inch Douglas fir, single blazed and scribed "RS 583 BT" bears North 60° West 39.8 feet.

A 22.0 inch Douglas fir, single blazed and scribed "RS 583 BT" bears South 68° East 10.8 feet.

Compass variation 20°00' East. Distances to face of blaze.

Field work by R. Vincent and K. Freudenberger.

December 31, 1963.

