

Survey No. 2409

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To remonument and perpetuate the 1/4 section corner common to Sections 5 and 4, Township 33 South, Range 3 East, W. M.

PROCEDURE: Found original Southeast BT which is now a 12.2 inch Douglas fir with both faces open and scribe "1/4 S" "BT" exposed, also badly decayed 4 inch x 4 inch Fir stake scribed "C.S.". After checking the position of this stake with the record to the Southeast BT, we removed said stake and set in its place a 1 inch by 36 inch galvanized steel pipe driven 32 inches in the ground and capped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

1963

T 33 S R 3 E

5/4

1/4 COR

RS 583

From this monument, the original Southeast BT bears South 40° East 15.6 feet to old face, and a 14.8 inch White Fir scribed "RS 583" "BT" bears North 3° 30' East 22.3 feet.

Compass variation 20°00' East. Distances to face of blaze.

Field work by R. Vincent and K. Freudenberger.

December 31, 1963

