

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250, OREGON REVISED STATUTES

FOR: ELK LUMBER COMPANY

PURPOSE: To rehabilitate and perpetuate the 1/4 section corner common to Sections 4 and 9, Township 32 South, Range 1 East, W. M.

PROCEDURE:

Found stone of approximately record dimensions with chisel marks "1/4" plainly visible, and remains of both original BT's. Both BT's are now down and badly deteriorated, but very faint scribing was found in the Southeast tree. Also found an old transit hub from some previous survey. This hub coincided with the corner point as determined by record bearings and distances from the BT's, so we removed it and set in its place a 1 inch by 36 inch galvanized steel pipe driven 30 inches in the ground and capped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

1963

T 32 S R 1E

S 4

S 9

1/4 COR

RS 583

From this monument a 9.5 inch Douglas fir bears North 16° 30' East 9.1 feet and an 8.0 inch Madrone bears South 55° West 33.5 feet. Both trees are scribed "RS 583 BT".

Compass variation was 20°00' East.

Distances to face of blaze.

Field work by R. Vincent, B. Brandt and D. Pfaff.

December 30, 1963.

