

2464

Written narrative to accompany plat for Survey No. _____

Survey for Mr W.G. Beard, 1702 Ridgeway, Medford, Oregon.

Located in Section 8, T. 37S. R. 1 W. Jackson County, Oregon.

Date March 24, 1964 Bearings from previous work.

Purpose to stake out 10 Acre tract along West and South lines.

Procedure: To get up the south line which is the line through the center of Section 8, it was necessary to get up the 1/4 section corner location by proportionate distance along the east line of Section 8, using the 1 1/2" pipe for the corner of Sections 5, 4, 8 and 9 and running to the 2" pipe for the corner of Sections 8, 9, 17 and 16, then returning and set a 1" x 32" pipe flush with the ground for the East 1/4 corner, from which a 3/4" pipe bears South 5/9 feet, a 22" pear Tree bears S 45°W 52.0 feet and a 5" cherry bears N 1°30'W 35.0 feet

Next to set the center of Section 8 we were able by using tall sights to see across the section to the 5/8" bar, 1/4 Corner on the west line of section 8, and set straddle lines at the fence corner, next from the 1/4 Corner to sections 5 and 8, we sighted on the 1 1/4" pipe for the 1/4 Corner to sections 8 and 17 and made a string intersection for the center of Section 8, and drove a 1" X 30" pipe from which the N/S- E/W fence corner bears S 67°W 3.3 feet, 8" pear bears S 65°40'E 10.0 feet, a 5/8" X 30" bolt for the center of the north and south street bears N 89°54'30"W 653.90 feet.

Next from these controls and the ones set for the street pattern previously reported we staked the ten acre tracts as shown.

