

Butte Falls, Oregon

3-4-64

Please record the following information pertaining to the surveys of the United States Public lands.

OBJECT; To remonument the Township corner common to;

T33S, R1E / T33S, R2E Willamette  
T34S, R1E / T34S, R2E Meridian

Original evidence found; (calls)

40" Fir	S20°E	46	links - rotted stump
24" "	N30°E	42	" - " "
28" "	N17°W	33	" - possible stump hole
38" "	S60°W	34	" - down, old face, no scribes visible

Old original blazes running N & S, scattered few blazes E & W.

To reenforce this positioning of Township corner, chained South call distance of 5.35 chains, found down called for 50" Fir line tree with vee hacks on N & S. Chained North 10.50 chains call distance to small stream (present channel approximately 6 feet North). Following blazes West located called for stream and 36" Cedar (called for Redwood) in approximate correct positions.

Set 2"x4' pipe:

$\frac{36}{1} / \frac{31}{6}$   
RS 461

Scribed RS 461 BT  
14" W. Fir N40°E 29.5'  
8" " S76°E 7.4'  
11" D. Fir N44°W 14.3'  
8" W. Fir S35°W 15.2'

