

CRATER LAKE AVE

REDDY AVE

LINDLEY ST

90°04'30"

89°54'30"

Survey for Bob Hart, Century Bldg,  
E. Main Street, Medford, Oregon.

In NE 1/4 of NE 1/4 S 30 T 37S.R 1 W.  
Jackson County, Oregon.  
Date March 31, 1964

Angle closures from a 1952 Survey of Block

REGISTERED  
OREGON  
LAND SURVEYOR  
*L. N. Dow*  
MAY 6, 1949  
L. N. DOW  
251

RECEIVED  
JACKSON  
APR 27 1964  
SUNNIV &  
SURVEY CO

Scale 1" = 100'

14.87  
5/8" x 24" bar set  
1/2" pipe f perfect

53.75  
5/8" x 24" bars  
90°10'  
15.00  
50.00

2470  
2470  
103.28  
90°10'  
89°54'30"

115.00  
set 5/8" x 24" bar  
5/8" bars f  
152  
set 5/8" x 24" bar  
105.0  
90°10'

89°51'

S.E. Cor. D.L.C. 42

E MAIN ST

1008.04

3/4" pipe 0.5S & 1.0W

Written narrative to accompany plat for Survey NO. 2488

Survey for Mr. Bob Hart, Century Bldg. Mendford, Oregon.

Located in the NE 1/4 of the NE 1/4 of S 30, T.37S. R 1W.  
Jackson County, Oregon.

Date March 31, 1964.

Purpose to stake out tract next to a 14 foot alley between  
Crater Lake Avenue and Lindley Avenue.

Procedure:

From a 1952 survey we had angular closures around the area.

Chaining from the SE Cor of D.L.C. NO. 42, a distance of 1008-04 feet and then running north parallel to the line of lindley Avenue for a distance of 30.00 feet we set a 5/8" x 24" bar for the intersection of the west line of the alley with the north line of East main Street leaving record distances of 152 and 14 foot alley to Lindley Street then chaining west on the north line of east Main Street at a distance of 103.28 feet we find a 1/2" pipe exactly correct for line and distance. Note that 1.0 foot west and 05 foot south is a 3/4" pipe N.G. We then set up control for the alley line at Reddy Avenue and staked the project as shown using 5/8" x 24" bars set nearly flush to 2" up.

