

2497

Butte Falls, Oregon
April 13, 1964

County Surveyor
Jackson County Courthouse
Medford, Oregon

Dear Sir;

Please record the following information pertaining to the surveys of the U. S. Public Lands.

Object: To remanument and scribe new BTs for found $\frac{1}{4}$ corner between Sections 17 and 18, T34S, R2E, W. N.

Original evidence found:-

Mound and post (no scribes)

36" Y. Pine stump S86°W 508 lks, face opened up
12" W. Oak N49°E 314 lks, " " " rotted

Scribed new BTs;- RS 461 BT

12" W. Oak S1°W 99.3'

15" Y. Pine N87°E 18.5'

18/17

Set 2"x4' pipe marked, RS 461

REGISTERED
OREGON
LAND SURVEYOR

Duane A. Smeltzer

OCTOBER 24, 1958
DUANE A. SMELTZER
461