



RECEIVED
 JACKSON COUNTY
 SURVEYOR
 AUG - 3 1964

REGISTERED
 OREGON
 LAND SURVEYOR

J. A. Hoffbuhr
 NOVEMBER 7, 1947
 J. A. HOFFBUHR
 2 2 2

BOUNDARY SURVEY of PROPERTY

situate in
 Block 65 of Original Town of Medford
 Jackson County Oregon
 for
 Don Kahl

J.A. Hoffbuhr L.S. Medford, Ore.
 Scale: 1"=60' June 17, 1964
 o=Set 3/4" iron reinforcing pin
 •=iron monument case (no monument found)

SURVEY NO. 2563

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH - 209.250
OREGON REVISED STATUTES.

FOR: Donald Kahl
1902 Crater Lake Highway
Medford, Oregon.

LOCATION OF SURVEY: Lots 9 and 10 and the Northerly 39.00 feet
of Lot 11, Block 65 Of the Original Town of Medford.

SURVEY PROCEDURE: Monument cases with copper plugs set in
concrete were found and used for intersection control at
4th and Ivy and 5th and Ivy. The intersection of 5th and
Holly was established by projection of the center line of
5th by using the last mentioned monument and a brass cap
with an "X" in Monument case at 5th and Oakdale, to intersect
with the center line of Holly Street projected from a brass
cap with punch hole at 8th and Holly and 6th and Holly.
The intersection of 4th and Holly was established by the use
of this projection on Holly with line between the copper plug
in concrete at Grape and 4th and the same at 4th and Ivy.
The distances and angles as measured and proportioned are
shown on the attached map.

June 1964

J.A. Hoffbuhr
Registered Land Surveyor

