

Butte Falls, Oregon
December 3, 1964

County Surveyor
Jackson County Court House
Medford, Oregon

Public Lands Surveys;

OBJECT: To scribe new BT.

T. 34S, R2E, Will. Mer.

$\frac{1}{4}$ corner between Sections 5 & 4.
Found 2"x4' plugged pipe previously set and two BTs. (RS 461)
BT to west broke off, scribed new BT: RS 461 $\frac{1}{4}$ S BT
23" Hemlock S45°W 16.0 feet

OBJECT: To remonument existent corner.

T. 33S, R2E, Will. Mer.

$\frac{1}{4}$ corner between Sections 34 & 35.

Found Stone scribed $\frac{1}{4}$, rotted stub SW BT, stump hole SE BT.

Set 5/8"x3' RE-bar capped, stamped RS 461
34/35

Scribed RS 461

$\frac{1}{4}$ S
7" Cedar S62°W 15.0 feet
12" W. Fir N60°E 2.5 "

OBJECT: To remonument existent corner.

T. 35S, R2E, Will. Mer.

$\frac{1}{4}$ corner between Sections 23 & 26.

Found BT N69°W 16 links, $\frac{1}{4}$ S visible, dead stub.

Set 5/8" Re-bar capped 3' long. Stamped RS 461

$\frac{23}{26}$

Scribed RS 461

$\frac{1}{4}$ S
BT. 22" W. Fir N64°W 14.2 feet
6" " S76°E 58.5 "

