

2704

Butte Falls, Oregon
2-9-65

County Surveyor
Jackson County Courthouse
Medford, Oregon

Dear Sir;

Please record the following information pertaining to the Surveys
of Public Lands.

Object; To remonument existent corner.

T. 35S. R3E, Will. Mer.
corner common to ;

$\frac{21}{28} / \frac{22}{27}$

Original evidence; Sec. 22 BT.- down, rotted, parts of scribes
22 visible.
possible SW BT- down, face. Fit calls.
" SE BT- stump, burned face. " "

Set; 1 1/2" Aluminum cap on 5/8"x3' rebar marked ;

R.S 461
 $\frac{21}{28} / \frac{22}{27}$

Scribed RS 461 BT;

12" D. Fir	S68°W	51.6' to q
6" Y. Pine	S0 1/2°E	5.6' "
12" "	N22°W	47.3' "
7" "	N13°E	32.5' "

