

SURVEY NO. 2735

SURVEY NARRATIVE TO COMPLY WITH ORS 209.250, REVISED BY CHAPTER 555, O. L. 1963

FOR - ELK LUMBER COMPANY  
P. O. BOX 606, MEDFORD, OREGON

PURPOSE - To remonument and perpetuate the quarter section corner common to sections 6 and 7, Township 34 South, Range 1 West, Willamette Meridian.

PROCEDURE -

Found the original Northeast BT which is a dead and down 14 inch Black Oak with "1/4 S" scribe exposed and intact. Also found a 4 inch by 4 inch by 4 foot post at the corner point. The record location of the other original BT falls within an old logging road.

At the record bearing and distance from the original Northeast BT set a 1 inch by 36 inch galvanized steel pipe driven 30 inches in the ground.

From this pipe monument, an 11 inch Douglas fir bears North 60° West 14.8 feet and an 11 inch Black Oak bears South 18°30' East 47.3 feet. Both trees are double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower. Distances were measured to face of lower blaze and compass variation was set at 20°00' East.

Field work by R. Vincent, completed December 18, 1964.

